

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	200	200
25200110	SODDING, SALT TOLERANT	SQ YD	200	200
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	100	100
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17
40600300	AGGREGATE (PRIME COAT)	TON	83	83
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	62	62
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1481	1481
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	890	890
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	368	368
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	12	12
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4187	4187
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	100	100
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	500	500
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	5260	5260
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	35894	35894
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	676	676
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	200	200
44000600	SIDEWALK REMOVAL	SQ FT	500	500
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	270	270
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2123	2123
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1167	1167
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	252	252
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	534	534
55039700	STORM SEWERS TO BE CLEANED	FOOT	420	420
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5
60262700	INLETS TO BE RECONSTRUCTED	EACH	5	5
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	78	78
60404940	FRAMES AND GRATES, TYPE 23	EACH	5	5
60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4294	4294
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	542	542
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	34,150	34,150
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	7,696	7,696
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	240	240
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	638	638
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	716	716
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	271	271
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17,075	17,075
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,848	3,848
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	319	319
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	835	835
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	835	835
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1624	1624
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	208	208
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	132	132

\* SPECIALTY ITEM

P:\2009\ME09086\_VerVar\_Phil\CAD\W05\_Roosevelt\rd\Sh\ts\03-DIGL\_40-sh1-Roosevelt-500.dgn  
 FILE NAME : P:\2009\ME09086\_VerVar\_Phil\CAD\W05\_Roosevelt\rd\Sh\ts\03-DIGL\_40-sh1-Roosevelt-500.dgn  
 USER NAME : Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.0110 voice, 630.839.2566 fax  
 WWW.MPS-IL.COM

**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 6/1/2010	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**ROOSEVELT ROAD  
 BRISTOL AVENUE TO 9TH AVENUE**

**SUMMARY OF QUANTITIES**

F.A.P. RTE. 347	SECTION 2010-061-RS	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 3
CONTRACT NO. 60L40			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

P:\2009\ME09086\_VerVar\_Phil\CAD\W05\_Roosevelt\rd\Sh\ts\03-DIGL\_40-sh1-Roosevelt-500.dgn