

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 1000	NON-PARTICIPATING
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10	10	-
25200100	SODDING	SQ YD	10	10	-
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	63	63	-
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,046	1,024	22
40600300	AGGREGATE (PRIME COAT)	TON	21	20.5	0.5
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5	-
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	444	434.5	9.5
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	442	439	3
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	905	886	19
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	170	170	-
42400800	DETECTABLE WARNINGS	SQ FT	48	48	-
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2,879	2,658	221
44000600	SIDEWALK REMOVAL	SQ FT	170	170	-
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	157	157	-
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	158	158	-
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	210	210	-
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	365	365	-
48101200	AGGREGATE SHOULDERS, TYPE B	TON	75	75	-
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	4	4	-
60260100	INLETS TO BE ADJUSTED	EACH	2	2	-
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5	-
67100100	MOBILIZATION	LSUM	1	1	-
70102620	TRAFFIC CONTROL AND PROTECTION STANDARD 701501	LSUM	1	1	-
70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	LSUM	1	1	-
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,401	1,401	-
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	467	467	-
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,246	9,142	104
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	76	76	-
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	15	15	-
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	-
X4420132	CLASS D PATCHES (SPECIAL)	SQ YD	314	314	-

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM
 LICENSE NO. 061-077200-0001
 DATE 5/27/2009 10:55:55 AM
 FILE 090803-S00.sht



DESIGNED - DSH	REVISED - 10-09-09 PER IDOT REVIEW
DRAWN - KAR	REVISED - 5-27-10 PER IDOT REVIEW
CHECKED - RWL	REVISED -
DATE - 10-09-09	FILE - 090803-S00.sht

**VILLAGE OF BUFFALO GROVE, ILLINOIS
MAIN STREET ARRA (LAPP)
RESURFACING**

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2666	09-00096-00-RS	LAKE	18	3
C-91-126-10			CONTRACT NO. 63367	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-90036071				