

**SUMMARY OF QUANTITIES**

CODE NO.	PAY ITEM	UNIT	CONST. CODE
			1000
			TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	740
40600300	AGGREGATE (PRIME COAT)	TON	16
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3.8
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	407
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	285
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	828
44000195	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ YD	179
44201701	CLASS D PATCHES, TYPE I, 5 INCH	SQ YD	4
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	6
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	24
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	312
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	8,655
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	125
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300220	TEMPORARY PAVEMENT MARKING <b>LINE 4"</b>	FOOT	11,145
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	376
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	125
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,140
Δ X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52
Δ Z0004518	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 5"	SQ YD	179

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

Plotted: April 26, 2010 @ 9:03 AM By: Kris Plung - Tab: 03 Quantities - 22,34

COPYRIGHT © 2010 ENGINEERING ENTERPRISES, INC.



**Engineering Enterprises, Inc.**  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60554  
630.466.6700 / www.eeiweb.com

**VILLAGE OF CAMPTON HILLS**

NO.	DATE	REVISIONS

**McDONALD ROAD  
LAPP IMPROVEMENTS**

**SUMMARY OF QUANTITIES**

Path: H:\SUBPROJ\CH0903\DWG\FINAL ENG\CH0903-CVR