


SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE 1000	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1
25200110	SODDING, SALT TOLERANT	SQ YD	5
25200200	SUPPLEMENTAL WATERING	UNIT	5
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	14
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	810
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	322
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	127
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	689
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	125
42400800	DETECTABLE WARNINGS	SQ FT	12
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	8,078
44000195	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ YD	29
44000600	SIDEWALK REMOVAL	SQ FT	125
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	69
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1

SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE 1000	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	900
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	8,843
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	240
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	45
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	26
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	63
* 78300200	RAISED REFLECTIVE MARKER REMOVAL	EACH	63
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	190
X0321558	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE-1 FRAME, CLOSED LID	EACH	1
Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	29

* SPECIALTY ITEM



USER NAME	DESIGNED	REVISED
---	DJA	5-21-10
PLOT SCALE	DRAWN	REVISED
---	DJA	---
PLOT DATE	CHECKED	REVISED
---	MM	---
	DATE	REVISED
	04-28-10	---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE: NONE	SHEET NO. 2 OF 12 SHEETS
STA. TO STA.	

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2845	10-00131-00-RS	COOK	12	2
CONTRACT NO.			63480	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				