

F.A.P. RTE. 0362	SECTION 09-00168-08-TL	COUNTY DU PAGE	TOTAL SHEETS 39	SHEET NO. 2
FED. ROAD DIST. NO. 1	ILLINOIS	CONTRACT NO. 63484		

GENERAL PLAN NOTES:

1. PLAN SHEETS IDENTIFY CONSTRUCTION IN BOLD PRINT, EXISTING ROADWAY ELEMENTS INCLUDED FOR REFERENCE ONLY ARE IDENTIFIED IN GRAYSCALE PRINT.
2. EXISTING CONDITIONS, INCLUDING THE CONDITION AND AVAILABILITY OF CONDUITS MUST BE FIELD VERIFIED BY THE CONTRACTOR.
3. THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE THE INSTALLATION OF ANY COMPONENT OF THE TRAFFIC SIGNAL SYSTEM. FOR LOCATION OF UTILITIES , CALL J.U.L.I.E. TOLL FREE NUMBER 1-800-892-0123.
4. THE CENTERLINE OF CONSTRUCTION IS THE CENTERLINE OF THE ROADWAY OR ROADWAY MEDIANS.
5. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF ALL EXISTING TRAFFIC SIGNAL AND LIGHTING FACILITIES IN THE PROJECT LIMITS. IF THERE ARE ANY QUESTIONS CONCERNING EXISTING EQUIPMENT THE CONTRACTOR SHALL CONTACT THE DUPAGE COUNTY DIVISION OF TRANSPORTATION AT (630)-407-6900 FOR TRAFFIC SIGNAL CABLE LOCATIONS A MINIMUM OF 48 HOURS IN ADVANCE (SATURDAYS, SUNDAYS AND HOLIDAYS EXCLUDED) AT ANY LOCATION WITHIN THE RIGHT-OF-WAY.
6. THE CONTRACTOR SHALL RETURN ALL REMOVED MASTER CONTROLLERS, CONTROLLERS AND CABINETS, UNLESS OTHERWISE MARKED ON THE PLANS, TO THE DUPAGE COUNTY TRAFFIC SIGNAL MAINTENANCE CONTRACTOR FACILITY AT 30W 751 NORTH AURORA ROAD, NAPERVILLE, IL 60563. ALL OTHER EQUIPMENT REMOVED SHALL BE SALVAGED BY THE CONTRACTOR WITH COSTS REFLECTED IN THE UNIT BID PRICES FOR THE RELATED PAY ITEMS.

DUPAGE COUNTY DIVISION OF TRANSPORTATION	
GENERAL NOTES	
SCALE: NONE	DESIGNED BY: TH
DATE: 4/23/10	CHECKED BY: DAZ