



EXISTING PHASE DESIGNATION DIAGRAM

EXISTING EMERGENCY VEHICLE PREEMPTION SEQUENCE





CHRISTOPHER B. BURKE
Syst West Higgins Road, Sulte 600
B Rosemort, Illinois 60018
(847) 823-0500

EXISTING EMERGENC	Y VEHICLE P	REEMPTORS
EMERGENCY VEHICLE PREEMPTOR	3	4
MOVEMENT		↓ ↑

TRAFFIC SIGNAL INSTALLATION					
ELECTRICAL SERVICE REQUIREMENTS					TOTAL WATTAGE
TYPE	NO. OF LAMPS	WAT XINCAND.		x % OPERATION	
SIGNAL (RED)	14		10	0.50	70.0
(YELLOW)	14		19	0.10	26.6
(GREEN)	14		11	0.40	61.6
ARROW	8		9	0.10	7.20
PED. SIGNAL	8		9	1.00	72.0
CONTROLLER	1		100	1.00	100.0
LUMINAIRE	-		250	0.50	_
L.E.D. ST. NAME SIGN	-		64	0.50	-
VIDEO SYSTEM	_		150	1.00	
BATTERY BACKUP	1		25	1.00	25.0
ENERGY COSTS	TO:			TOTAL =	362.40

1707 ST. JOHNS AVENUE

ENERGY SUPPLY: CONTACT: JEAN WILL
PHONE: (847) 816-5459

COMPANT:	COMED						
ILE NAME =	USER NAME = FBARISO	DESIGNE	D -	ABR	REVISED	-	
:\LCDOT\090407\Traffic\CAB_LCRD-TurnBull.dgn		DRAWN		FPB / FCP	REVISED		
	PLDT SCALE = NOT TO SCALE	CHECKED) -	MJT	REVISED	-	
	PLOT DATE = 5/3/2010	DATE		APRIL 30, 2010	REVISED		

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

ROAD

89

1

SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM AND EMERGENCY VEHICLE PREEMPTION SEQUENCE LAKE 76 18 LAKE COOK ROAD AND TURNBULL WOODS COURT CONTRACT NO. 63485 SCALE: NOT TO SCALE SHEET NO. -- OF -- SHEETS STA. --

CABLE PLAN

EACH CONTROLLER AND CABINET (COMPLETE) EACH SERVICE INSTALLATION

CONSTRUCTION NOTES:

- $\langle\overline{1}\rangle$ all existing confirmation beacons shall be retrofitted with LeD indications. This work shall be included in the cost for the Pay ITEM: UNINTERRUPTIBLE POWER SUPPLY.
- ② RELOCATE EXISTING LIGHT DETECTOR AMPLIFIER TO NEW CONTROLLER CABINET.
- (3) THE TRAFFIC SIGNAL CONTROLLER SHALL BE NTCIP COMPATIBLE.
- 4 INSTALL NEW POLE MOUNT SERVICE INSTALLATION. INSTALL SERVICE GROUND CABLE IN EXISTING CONDUIT.
- (5) A MANUAL PHASE ADVANCE SWITCH SHALL BE PROVIDED. THIS SHALL BE INCLUDED IN THE COST FOR THE PAY ITEM: FULL ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL.

GARDEN

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE
DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE
SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE
CONTRACT BID PRICE.

LAKE COOK

POLE MOUNT SERVICE INSTALLATION

SCHEDULE OF QUANTITIES

TRACER CABLE

INTERCONNECT TO GREEN BAY ROAD

SCHEDULE OF QUANTITIES		
ITEM	UNIT	TOTAL
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
SERVICE INSTALLATION - POLE MOUNTED	EACH	1
UNINTERRUPTIBLE POWER SUPPLY	EACH	1
LAYER II (DATALINK) SWITCH	EACH	1
DRILL EXISTING HANDHOLE	EACH	2
INDUCTIVE LOOP DETECTOR	EACH	7
ELECTRIC CABLE IN CONDUIT, GROUNDING NO. 6 1C	FOOT	40

THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

EXISTING EMERGENC	Y VEHICLE P	REEMPTORS
EMERGENCY VEHICLE PREEMPTOR	3	4
MOVEMENT		↓ ↑

TRAFFIC SIGNAL INSTALLATION ELECTRICAL SERVICE REQUIREMENTS						
TVDE	NO OF 1 11/00	WATT	TAGE	W 0050477011	WATTAGE	ĺ
TYPE	NO. OF LAMPS	XINCAND.	LED >	% OPERATION		ĺ
IGNAL (RED)	14		10	0.50	70.0	ĺ
(YELLOW)	14		19	0.10	26.6	ĺ
(GREEN)	14		11	0.40	61.6	1
RROW	8		9	0.10	7.20	
ED. SIGNAL	8		9	1.00	72.0	ĺ
ONTROLLER	1		100	1.00	100.0	
.UMINAIRE	-		250	0.50	-	
.E.D. ST. NAME SIGN	-		64	0.50	-	
IDEO SYSTEM	_		150	1.00		
SATTERY BACKUP	1		25	1.00	25.0	

CITY OF HIGHLAND PARK

HIGHLAND PARK, IL 60035-3593

INTERCONNECT TO

TRACER CABLE-