


GREEN BAY --②--DUAL ENTRY PHASE PEDESTRIAN PHASE NUMBER REFERS TO ASSOCIATED PHASE

EXISTING PHASE DESIGNATION DIAGRAM

EXISTING EMERGENCY VEHICLE PREEMPTION SEQUENCE





GREEN BAY

CHRISTOPHER B. 9575 West Higgins Road, Rosemont, Illinois 60018 (847) 823-0500

EXISTING EMERGENC	Y VEHICLE F	PREEMPTORS
EMERGENCY VEHICLE PREEMPTOR	3	4
MOVEMENT	<del></del>	1

	L.C.D. AFFIC SIGNAL TRICAL SERVIO	TOTAL			
TYPE		WATT		× % OPERATION	WATTAGE
SIGNAL (RED)	8		10	0.50	40.0
(YELLOW)	8		19	0.10	15.2
(GREEN)	8		11	0.40	35.2
ARROW	4		9	0.10	3.6
PED. SIGNAL	6		9	1.00	54.0
CONTROLLER	- 1		100	1.00	100.0
LUMINAIRE	_		250	0.50	-
L.E.D. ST. NAME SIGN	-		64	0.50	
VIDEO SYSTEM	_		150	1.00	_
BATTERY BACKUP	1		25	1.00	25.0
ENERGY COSTS	TO:			TOTAL =	273.0

## CITY OF HIGHLAND PARK


1707 ST. JOHNS AVENUE HIGHLAND PARK, IL 60035-3593

THE FOLLOWING ITEMS SHALL BE REMOVED BY THE CONTRACTOR AND SHALL BE DISPOSED OF BY THEM OUTSIDE THE RIGHT-OF-WAY AT THEIR EXPENSE. THE SALVAGE VALUE OF THE REMOVED EQUIPMENT SHALL BE REFLECTED IN THE CONTRACT BID PRICE.

1 EACH CONTROLLER

CONSTRUCTION NOTES:

- 1 INSTALL UNINTERRUPTIBLE POWER SUPPLY (UPS).
- ② ALL EXISTING CONFIRMATION BEACONS SHALL BE RETROFITTED WITH LED INDICATIONS. THIS WORK SHALL BE INCLUDED IN THE COST FOR THE PAY ITEM: UNINTERRUPTIBLE POWER SUPPLY.
- 3 THE TRAFFIC SIGNAL CONTROLLER SHALL BE NTCIP COMPATIBLE.



## SCHEDULE OF QUANTITIES

ITEM	UNIT	TOTAL
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
FULL-ACTUATED CONTROLLER IN EXISTING CABINET, SPECIAL	EACH	1
MODIFY EXISTING CONTROLLER CABINET	EACH	1
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
UNINTERRUPTIBLE POWER SUPPLY	EACH	1
LAYER II (DATALINK) SWITCH	EACH	1
SPLICE FIBER IN CABINET	EACH	6
TERMINATE FIBER IN CABINET	EACH	12

THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

	COMI AIVI:	CONILD				
	FILE NAME =	USER NAME = FBARISO	DESIGNED	-	ABR	REVISED -
I	N:\LCDOT\090407\Traffic\CAB_GBRD-Renaissance.	gn	DRAWN	***	FPB / FCP	REVISED -
		PLOT SCALE = NOT TO SCALE	CHECKED	-	MJT	REVISED -
ı		PLOT DATE = 5/3/2010	DATE	-	APRIL 30, 2010	REVISED -

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** 

SCHEDULE OF QUANTITIES, CABLE PLAN, PHASE DESIGNATION DIAGRAM		SECTION	COUNTY	TOTAL	SHEET NO.
AND EMERGENCY VEHICLE PREEMPTION SEQUENCE		06-00924-00-TL	LAKE	76	29
GREEN BAY ROAD AND RENAISSANCE GARAGE			CONTRACT	NO. 6	3485
E. NOT TO SCALE SHEET NO OF SHEETS STA TO STA		TILINOIS FED. AT	D PROJECT		