

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY J000 80% FED 20% STATE
50101200	REMOVAL OF EXISTING STRUCTURES NO. 10	EACH	3	3
50101300	REMOVAL OF EXISTING STRUCTURES NO. 11	EACH	1	1
50101400	REMOVAL OF EXISTING STRUCTURES NO. 12	EACH	1	1
50104400	CONCRETE HEADWALL REMOVAL	EACH	9	9
50200100	STRUCTURE EXCAVATION	CU YD	6895	6895
50800105	REINFORCEMENT BARS	POUND	26883	26883
51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	3918	3918
51202230	FURNISHING SOLDIER PILES (W SECTION)	FOOT	9757	9757
51205200	TEMPORARY SHEET PILING	SQ FT	38036	38036
51500100	NAME PLATES	EACH	28	28
52000030	PREFORMED JOINT SEAL 2 1/2"	FOOT	147	147
52000050	PREFORMED JOINT SEAL 4"	FOOT	163	163
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	1	1
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1	1
54001003	BOX CULVERT END SECTION, CULVERT NO.3	EACH	1	1
54001004	BOX CULVERT END SECTION, CULVERT NO.4	EACH	1	1
54001005	BOX CULVERT END SECTION, CULVERT NO.5	EACH	1	1
54001006	BOX CULVERT END SECTION, CULVERT NO.6	EACH	1	1
54001007	BOX CULVERT END SECTION, CULVERT NO.7	EACH	1	1
54001008	BOX CULVERT END SECTION, CULVERT NO.8	EACH	2	2
54001009	BOX CULVERT END SECTION, CULVERT NO.9	EACH	2	2
54001010	BOX CULVERT END SECTION, CULVERT NO.10	EACH	2	2
54001011	BOX CULVERT END SECTION, CULVERT NO.11	EACH	2	2
54003000	CONCRETE BOX CULVERTS	CU YD	160	160
54010504	PRECAST CONCRETE BOX CULVERT 5'x4'	FOOT	70	70
54010603	PRECAST CONCRETE BOX CULVERT 6'x3'	FOOT	146	146
54010705	PRECAST CONCRETE BOX CULVERT 7'x5'	FOOT	194	194
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	119	119
542A0265	PIPE CULVERTS, CLASS A, TYPE 1 60"	FOOT	77	77
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	301	301
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	158	158
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	296	296
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	160	160
542A1117	PIPE CULVERTS, CLASS A, TYPE 2 72"	FOOT	106	106
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	102	102
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	1142	1142

\* SPECIALTY ITEM

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct\pwwork\PWIDOT\CUSHMANBW\dms31213\dms31213.dwg	6608cwr.dgn	DRAWN -	REVISED -			742	37R-4	OGLE	867	5	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64E17					
PLOT DATE = Wed Apr 07 14:30:04 2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE:							
				SHEET NO. OF SHEETS STA. TO STA.							