

SCHEDULE OF QUANTITIES

20101000		TEMPORARY FENCE					
FOOT	LOCATION	REMARK'S					
300	LT. STA. 680 + 0	BIOLOGICAL PLANT MATERIAL at Const. Limits	TO	683 + 0			
300	LT. STA. 701 + 0	BIOLOGICAL PLANT MATERIAL at Const. Limits	TO	704 + 0			
310	LT. STA. 706 + 0	BIOLOGICAL PLANT MATERIAL at Const. Limits	TO	709 + 10			
121	LT. STA. 717 + 0	BIOLOGICAL PLANT MATERIAL at Const. Limits	TO	718 + 21			
150	RT. STA. 749 + 0	BIOLOGICAL PLANT MATERIAL at Const. Limits	TO	750 + 50			
58	LT. STA. 764 + 50	NATIVE AMERICAN BURIAL MOUND (See Commitment #17 in General Notes)	TO	765 + 0			
350	LT. STA. 806 + 0	BIOLOGICAL PLANT MATERIAL at Const. Limits	TO	809 + 50			
500	LT. STA. 830 + 0	WETLAND AREA	TO	835 + 0			
137	RT. STA. 868 + 63	BIOLOGICAL PLANT MATERIAL at Const. Limits	TO	870 + 0			
750	RT. STA. 901 + 50	BIOLOGICAL PLANT MATERIAL at Const. Limits	TO	909 + 0			
198	LT. STA. 1066 + 0	WETLAND AREA	TO	1067 + 98			
<u>3174</u>	TOTAL						

20101100		TREE TRUNK PROTECTION					
EACH	LOCATION	REMARK'S					
400	680 + 0	Use to be determined by Resident Engineer (Project Limits)	TO	1068 + 0			
<u>400</u>	TOTAL						

25000775		SELECTIVE MOWING STAKES					
EACH	LOCATION	REMARK'S					
8	LT. STA. 1013 + 0	PRAIRIE MITIGATION AREA (250' SPACING ALONG IL 2)	TO	1030 + 0			
<u>8</u>	TOTAL						

25100900		TURF REINFORCEMENT MAT					
SQ. YD	LOCATION	REMARK'S					
5.8	LT. STA. 680 + 7	Outlet (6.5' W x 8' L)					
20.0	LT. STA. 705 + 9	Dropbox at AR Culvert (12'x15')					
42.7	LT. STA. 740 + 79	Dropbox at AR Culvert (24'x16')					
74.7	LT. STA. 747 + 50	Dropbox at AR Culvert (24'x28')					
3.0	LT. STA. 768 + 96	Silver Creek SW (3'x9')					
3.0	LT. STA. 771 + 0	Silver Creek NW (3'x9')					
24.0	LT. STA. 792 + 26	Dropbox at AR Culvert (12'x18')					
57.3	LT. STA. 804 + 40	12'x43'	TO	804 + 67			
35.3	LT. STA. 804 + 52	6'x53'	TO	805 + 1			
5.8	LT. STA. 875 + 1	Outlet (6.5' W x 8' L)					
442.0	RT. STA. 923 + 50	Ditch Bottom Protection (6.5' W)	TO	929 + 62			
20.0	LT. STA. 942 + 31	Dropbox at AR Culvert (12'x15')					
5.8	LT. STA. 945 + 19	Outlet (6.5' W x 8' L)					
168.0	LT. STA. 964 + 0	Dropbox at AR Culvert (42'x36')					
5.8	LT. STA. 970 + 92	Outlet (6.5' W x 8' L)					
64.0	LT. STA. 974 + 38	Dropbox at AR Culvert (24'x24')					
58.7	LT. STA. 986 + 88	Dropbox at AR Culvert (24'x22')					
64.0	LT. STA. 1011 + 71	Grated End Section (16'x36')					
42.7	LT. STA. 1023 + 85	Grated End Section (16'x24')					
5.8	LT. STA. 1030 + 8	Outlet (6.5' W x 8' L)					
42.7	LT. STA. 1042 + 23	Grated End Section (16'x24')					
42.7	LT. STA. 1050 + 36	Grated End Section (16'x24')					
<u>1233.6</u>	TOTAL						

28000250		TEMPORARY EROSION CONTROL SEEDING					
POUND	LOCATION	REMARK'S					
56200	LT/RT 680 + 0	ESTIMATED QUANTITY (PROJECT LIMITS)	TO	1068 + 0			
<u>56200</u>	TOTAL						

28000305		TEMPORARY DITCH CHECKS					
FOOT	LOCATION	REMARK'S					
20	LT. STA. 716 + 5	100' spacing	TO	717 + 88			
20	LT. STA. 747 + 50	100' spacing	TO	749 + 50			
30	LT. STA. 751 + 0	100' spacing	TO	754 + 0			
120	LT. STA. 755 + 0	100' spacing	TO	765 + 42			
10	RT. STA. 750 + 0	100' spacing	TO	751 + 0			
30	RT. STA. 762 + 50	75' spacing	TO	765 + 30			
20	LT. STA. 766 + 0	100' spacing	TO	767 + 0			
20	LT. STA. 784 + 0	50' spacing	TO	785 + 33			
80	LT. STA. 786 + 0	50' spacing	TO	788 + 0			
70	LT. STA. 788 + 41	50' spacing	TO	792 + 26			
20	RT. STA. 792 + 48	50' spacing	TO	790 + 0			
110	LT. STA. 792 + 26	100' spacing	TO	803 + 0			
170	LT. STA. 805 + 0	75' spacing	TO	818 + 33			
60	LT. STA. 819 + 0	100' spacing	TO	824 + 30			
10	LT. STA. 824 + 30	100' spacing	TO	825 + 64			
80	LT. STA. 826 + 0	100' spacing	TO	833 + 33			
90	LT. STA. 851 + 0	100' spacing	TO	860 + 66			
20	LT. STA. 860 + 66	50' spacing	TO	861 + 50			
20	LT. STA. 898 + 0	50' spacing	TO	899 + 50			
80	LT. STA. 899 + 50	50' spacing	TO	904 + 0			
70	RT. STA. 899 + 50	50' spacing	TO	903 + 66			
20	RT. STA. 903 + 77	100' spacing	TO	907 + 0			
110	LT. STA. 905 + 0	50' spacing	TO	911 + 33			
40	RT. STA. 907 + 50	50' spacing	TO	909 + 50			
190	RT. STA. 923 + 50	50' spacing	TO	929 + 62			
20	LT. STA. 931 + 93	100' spacing	TO	934 + 36			
10	LT. STA. 934 + 57	100' spacing	TO	937 + 0			
10	LT. STA. 937 + 0	100' spacing	TO	938 + 6			
40	LT. STA. 938 + 26	100' spacing	TO	942 + 31			
30	LT. STA. 944 + 14	100' spacing	TO	948 + 82			
10	LT. STA. 949 + 15	100' spacing	TO	951 + 15			
10	LT. STA. 952 + 45	100' spacing	TO	953 + 85			
50	LT. STA. 954 + 30	100' spacing	TO	959 + 41			
30	LT. STA. 960 + 50	100' spacing	TO	964 + 0			
20	LT. STA. 965 + 20	100' spacing	TO	967 + 50			
20	LT. STA. 971 + 0	100' spacing	TO	974 + 38			
10	LT. STA. 977 + 44	100' spacing	TO	979 + 41			
10	LT. STA. 979 + 52	100' spacing	TO	981 + 19			
50	LT. STA. 981 + 35	100' spacing	TO	986 + 88			
20	RT. STA. 975 + 0	100' spacing	TO	976 + 77			
50	RT. STA. 977 + 30	100' spacing	TO	982 + 50			
100	LT. STA. 1006 + 0	100' spacing	TO	1010 + 58			
80	LT. STA. 1014 + 0	100' spacing	TO	1021 + 0			
350	LT. STA. 1022 + 25	100' spacing	TO	1023 + 85			
350	LT. STA. 1023 + 85	100' spacing	TO	1025 + 60			
140	LT. STA. 1025 + 62	100' spacing	TO	1030 + 50			
10	LT. STA. 1036 + 50	100' spacing	TO	1039 + 0			
50	LT. STA. 1039 + 49	100' spacing	TO	1042 + 23			
20	LT. STA. 1042 + 23	100' spacing	TO	1044 + 77			
160	LT. STA. 1044 + 77	100' spacing	TO	1050 + 36			
10	LT. STA. 1050 + 36	100' spacing	TO	1052 + 37			
30	LT. STA. 1052 + 37	100' spacing	TO	1056 + 0			
30	LT. STA. 1064 + 0	100' spacing	TO	1066 + 0			
Town Hall Rd.	RT. STA. 88 + 50	33' spacing	TO	89 + 50			
Camling Rd.	LT. STA. 96 + 50	33' spacing	TO	99 + 80			
Camling Rd.	RT. STA. 96 + 50	33' spacing	TO	99 + 40			
Townline Rd.	RT. STA. 146 + 27	20' spacing	TO	149 + 34			
<u>410</u>	Various locations as determined by the Resident Engineer (Estimated Quantity)						
<u>3970</u>	TOTAL						

28000250		TEMPORARY EROSION CONTROL SEEDING					
POUND	LOCATION	REMARK'S					
56200	LT/RT 680 + 0	ESTIMATED QUANTITY (PROJECT LIMITS)	TO	1068 + 0			
<u>56200</u>	TOTAL						

28000400		PERIMETER EROSION BARRIER					
SILT FENCE	FOOT	LOCATION	REMARK'S				
2950	RT. STA. 683 + 0	For Articulated Block Revetment Mat (Embankment)	TO	712 + 50			
232	LT. STA. 718 + 52		TO	720 + 62			
45	RT. STA. 713 + 0		TO	713 + 45			
408	RT. STA. 713 + 55		TO	717 + 63			
234	RT. STA. 718 + 62		TO	720 + 87			
559	LT. STA. 721 + 72	Along Mud Creek Rd.	TO	5 + 75			
10	RT. STA. 726 + 90		TO	727 + 0			
235	RT. STA. 727 + 10		TO	729 + 45			
140	RT. STA. 729 + 55		TO	730 + 95			
140	RT. STA. 731 + 5		TO	732 + 45			
140	RT. STA. 732 + 55		TO	733 + 95			
140	RT. STA. 734 + 5		TO	735 + 45			
140	RT. STA. 735 + 55		TO	736 + 95			
140	RT. STA. 737 + 5		TO	738 + 45			
140	RT. STA. 738 + 55		TO	739 + 95			
69	RT. STA. 740 + 5		TO	740 + 74			
211	RT. STA. 740 + 84		TO	742 + 95			
88	RT. STA. 743 + 5		TO	743 + 93			
103	RT. STA. 744 + 42		TO	745 + 45			
190	RT. STA. 745 + 55		TO	747 + 45			
145	RT. STA. 747 + 55		TO	749 + 0			
200	RT. STA. 751 + 0		TO	753 + 0			
500	RT. STA. 754 + 0		TO	759 + 0			