SCHEDULE OF QUANTITIES

50101200 REMOVAL OF EXISTING STRUCTURES NO. 10

EACH		LOCATION	REMARK'S
1	LT/RT	804 + 63	4x6.5 Concrete Box Culvert
1	LT/RT	922 + 38	4x5.5 Concrete Box Culvert
1	LT/RT	986 + 83	4x3 Concrete Box Culvert
3	TOTAL		

50101300 REMOVAL OF EXISTING STRUCTURES NO. 11

EACH		LOCATION	REMARK'S
1	LT. STA.	147 + 73	16'x22' Concrete Bridge for Old Rt. 2
1	TOTAL		

50101400 REMOVAL OF EXISTING STRUCTURES NO. 12

EACH		LOCATION	REMARK'S
1	LT. STA.	804 + 54	10'x17' Concrete Bridge for Old Rt. 2
1	TOTAL		

50104400 CONCRETE HEADWALL REMOVAL

EACH		LOCATION	REMARK'S
1	LT. STA.	750 + 48	S. of Indian Cove Drive
1	RT. STA.	754 + 39	N. of Indian Cove Drive
1	LT. STA.	766 + 93	
1	LT. STA.	767 + 13	
1	LT. STA.	788 + 10	
1	LT. STA.	788 + 58	
1	LT. STA.	895 + 46	
1	RT. STA.	895 + 46	
1	RT. STA.	147 + 0	Town Line Rd.
9	TOTAL		

51500100 NAME PLATES

EACH		LOCATION	REMARK'S
1		705 + 9	SN 071-1205
1		716 + 5	SN 071-1208
1		740 + 79	SN 071-1163
1		747 + 50	SN 071-1204
1		784 + 0	SN 071-1206
1		792 + 26	SN 071-1207
1		804 + 56	SN 071-1134
1		818 + 33	SN 071-1210
1		824 + 30	SN 071-1211
1		833 + 77	SN 071-1135
1		860 + 66	SN 071-1212
1		895 + 46	SN 071-1213
1		899 + 50	SN 071-1214
1		942 + 31	SN 071-1215
1		951 + 15	SN 071-1216
1		964 + 0	SN 071-1128
1		974 + 38	SN 071-1136
1		986 + 88	SN 071-1217
1		995 + 90	SN 071-1209
1		1010 + 58	SN 071-1218
1		1011 + 71	SN 071-1137
1		1023 + 85	SN 071-1138
1		1042 + 23	SN 071-1129
1		1050 + 36	SN 071-1130
1		To be determhed by Resident Engineer	SN 071-7003 Retaining Wall
1		To be determhed by Resident Engineer	SN 071-7004 Retaining Wall
1		To be determhed by Resident Engineer	SN 071-7005 Retaining Wall
1		To be determhed by Resident Engineer	SN 071-7006 Retaining Wall
28	TOTAL		

52000030 PREFORMED JOINT SEAL 2 1/2"

FOOT		LOCATION			REMARK'S
61	STA.	720 + 40	TO	722 + 22	Mudd Creek Bridge SN 071-0025
86	STA.	769 + 20	TO	770 + 76	Silver Creek Bridge SN 071-0024
147	TOTAL				

52000050 PREFORMED JOINT SEAL 4"

FOOT		LOCATION			REMARK'S
64	STA.	720 + 40	TO	722 + 22	Mudd Creek Bridge SN 071-0025
99	STA.	912 + 57	TO	915 + 89	Leaf River Bridge SN 071-0087
163	TOTAL				

542D0235 PIPE CULVERTS, CLASS D, TYPE 1 30"

FOOT		LOCATION	REMARK'S
27	LT. STA.	725 + 36	Extend existing 30" CMP (Connecting Band Included in the cost of the pipe culvert)
27	TOTAL		

54213447 END SECTIONS, 12"

EACH		LOCATION	REMARK'S
1	LT. STA.	768 + 96	Silver Creek SW
1	RT. STA.	768 + 96	Silver Creek SE
1	LT. STA.	771 + 0	Silver Creek NW
1	RT. STA.	771 + 0	Silver Creek NE
4	TOTAL		

54213465 END SECTIONS 30"

EACH		LOCATION	REMARK'S
1	LT. STA.	725 + 36	Extend existing 30" CMP
1	TOTAL		

60100060 CONCRETE HEADWALL FOR PIPE DRAINS

EACH		LOCATION	REMARK'S
1	RT. STA.	714 + 50	
1	RT. STA.	717 + 50	
1	LT. STA.	725 + 73	
1	RT. STA.	725 + 73	
1	RT. STA.	726 + 0	
1	RT. STA.	729 + 0	
1	RT. STA.	732 + 0	
1	RT. STA.	735 + 0	
1	RT. STA.	738 + 0	
1	RT. STA.	741 + 0	
1	RT. STA.	744 + 0	
1	RT. STA.	747 + 0	
1	RT. STA.	749 + 89	
1	RT. STA.	752 + 14	
1	RT. STA.	754 + 39	
1	RT. STA.	772 + 0	
1	RT. STA.	780 + 50	
1	RT. STA.	783 + 50	
1	RT. STA.	786 + 50	
1	RT. STA.	789 + 50	
1	RT. STA.	792 + 50	
1	RT. STA.	795 + 50	
1	RT. STA.	798 + 50	
1	LT. STA.	771 + 50	
1	LT. STA.	774 + 50	
1	LT. STA.	777 + 50	
1	LT. STA.	780 + 50	
1	LT. STA.	783 + 50	
1	LT. STA.	786 + 50	
1	LT. STA.	789 + 50	
1	LT. STA.	792 + 50	
1	LT. STA.	795 + 50	
1	LT. STA.	798 + 50	
1	LT. STA.	802 + 89	
1	LT. STA.	817 + 39	
1	LT. STA.	819 + 89	
1	LT. STA.	822 + 39	
1	LT. STA.	824 + 89	
1	LT. STA.	826 + 50	
1	LT. STA.	840 + 0	
1	LT. STA.	842 + 0	
1	LT. STA.	844 + 0	
1	LT. STA.	846 + 0	
1	LT. STA.	848 + 0	
1	LT. STA.	862 + 0	
1	LT. STA.	884 + 0	
1	LT. STA.	886 + 75	
1	LT. STA.	889 + 50	
1	LT. STA.	892 + 25	
1	LT. STA.	895 + 0	
1	LT. STA.	897 + 75	
1	LT. STA.	900 + 50	
1	LT. STA.	907 + 50	
1	LT. STA.	909 + 39	
1	RT. STA.	830 + 0	
1	RT. STA.	833 + 0	
1	RT. STA.	836 + 0	
1	RT. STA.	839 + 0	
1	RT. STA.	842 + 0	
1	RT. STA.	845 + 0	
1	RT. STA.	848 + 0	
1	RT. STA.	851 + 0	
1	RT. STA.	854 + 0	
1	RT. STA.	857 + 0	
1	RT. STA.	860 + 0	
1	RT. STA.	863 + 0	