

SCHEDULE OF QUANTITIES

70301000 WORKZONE PAVEMENT MARKING REMOVAL

SO. FT.	LOCATION	REMARK'S
250	FOR HMA SIDEROADS	
100	RT. STA. 1188 + 62 TO 1191 + 62	Estimated Quantity
147	RT. STA. 1068 + 0 TO 1072 + 42	IL 72 - Edge Line - STAGE 2
143	LT. STA. 1188 + 62 TO 1191 + 62	IL 2 - Edge Line - STAGE 2
54	LT. STA. 1067 + 92 TO 1069 + 55	IL 72 - Edge Line - STAGE 2
97	LT. STA. 1069 + 55 TO 1072 + 42	IL 2 - Edge Line - STAGE 2
108	LT. STA. 1188 + 68 TO 1191 + 91	IL 72 - Edge Line - STAGE 3
108	RT/LT 1188 + 68 TO 1191 + 92	IL 2 - Edge Line - STAGE 3
65	LT. STA. 1191 + 91 TO 1061 + 78	IL 72 Radius- Edge Line - STAGE 3
71	LT. STA. 1191 + 92 TO 1061 + 78	IL 72 Radius- Edge Line - STAGE 3
308	LT. STA. 1061 + 78 TO 1070 + 10	IL 2 - Edge Line - STAGE 3
279	LT. STA. 1061 + 78 TO 1070 + 10	IL 2 - Edge Line - STAGE 3
77	LT. STA. 1070 + 10 TO 1072 + 42	IL 2 - Edge Line - STAGE 3
78	LT/RT 1070 + 10 TO 1072 + 42	IL 2 - Edge Line - STAGE 3
1887	TOTAL	

70400100 TEMPORARY CONCRETE BARRIER

EQOT	LOCATION	REMARK'S
238	LT. STA. 1190 + 50 TO 1192 + 87	IL 72 - STAGE 1
88	LT. STA. 1192 + 87 TO 1061 + 8	IL 72 RADIUS - STAGE 1
850	LT. STA. 1061 + 8 TO 1069 + 60	IL 2 - STAGE 1
113	LT. STA. 1069 + 60 TO 1070 + 72	IL 2 - STAGE 1
1287.5	TOTAL	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

EQOT	LOCATION	REMARK'S
175	RT/LT 1190 + 17 TO 1191 + 92	IL 72 - STAGE 2
213	LT. STA. 1191 + 92 TO 1061 + 78	IL 72 RADIUS - STAGE 2
788	LT. STA. 1061 + 78 TO 1069 + 60	IL 72 - STAGE 2
113	LT/RT 1069 + 60 TO 1070 + 72	IL 72 - STAGE 2
1287.5	TOTAL	

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	REMARK'S
5	RT. STA. 679 + 90 TO 685 + 0	ø 125' spacing
3	RT. STA. 685 + 0 TO 697 + 0	ø 400' spacing
6	RT. STA. 697 + 0 TO 707 + 50	ø 175' spacing
1	RT. STA. 707 + 50 TO 711 + 50	ø 400' spacing
8	RT. STA. 711 + 50 TO 720 + 34	ø 125' spacing
2	LT. STA. 718 + 79 TO 720 + 4	ø 125' spacing
3	LT. STA. 722 + 29 TO 8 + 72	ø 125' spacing
4	RT. STA. 722 + 60 TO 725 + 15	ø 80' spacing
4	RT. STA. 725 + 15 TO 743 + 47	ø 400' spacing
3	RT. STA. 767 + 27 TO 768 + 77	ø 80' spacing
2	LT. STA. 768 + 2 TO 768 + 77	ø 80' spacing
2	RT. STA. 771 + 20 TO 771 + 95	ø 80' spacing
3	LT. STA. 771 + 19 TO 772 + 69	ø 80' spacing
6	RT. STA. 868 + 63 TO 872 + 75	ø 80' spacing
4	RT. STA. 872 + 75 TO 877 + 88	ø 150' spacing
4	RT. STA. 910 + 13 TO 912 + 26	ø 80' spacing
2	LT. STA. 911 + 98 TO 912 + 48	ø 80' spacing
6	LT. STA. 916 + 18 TO 919 + 62	ø 80' spacing
1	LT. STA. 919 + 62 TO 921 + 18	ø 400' spacing
6	RT. STA. 987 + 63 TO 991 + 63	ø 80' spacing
3	RT. STA. 991 + 63 TO 1002 + 38	ø 400' spacing
8	LT. STA. 1062 + 18 TO 1067 + 68	ø 80' spacing
4	RT. STA. 1065 + 18 TO 1067 + 68	ø 80' spacing
90	TOTAL	

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION	REMARK'S
1	RT. STA. 8 + 20	Along Mudd Creek Rd.
1	LT. STA. 718 + 31	Mudd Creek Structure
1	RT. STA. 743 + 97	South of Indian Cove Drive
1	RT. STA. 766 + 77	Silver Creek Structure
1	LT. STA. 767 + 52	Silver Creek Structure
1	RT. STA. 772 + 45	Silver Creek Structure
1	LT. STA. 773 + 19	Silver Creek Structure
1	RT. STA. 868 + 13	
1	RT. STA. 878 + 38	
1	RT. STA. 909 + 63	Leaf River Structure
1	LT. STA. 911 + 48	North of PE entrance at Lt. Sta. 911+43
1	LT. STA. 921 + 68	Leaf River Structure
1	RT. STA. 916 + 45	Leaf River Structure
1	RT. STA. 987 + 12	
1	RT. STA. 1002 + 87	
1	LT. STA. 1063 + 18	Mill Creek Structure
1	RT. STA. 1064 + 68	Mill Creek Structure
17	TOTAL	

78200520 BARRIER WALL MARKERS, TYPE B

EACH	LOCATION	REMARK'S
2	LT. STA. 720 + 55 TO 721 + 80	Mudd Creek Structure
2	RT. STA. 720 + 80 TO 722 + 5	Mudd Creek Structure
3	LT. STA. 768 + 90 TO 771 + 6	Silver Creek Structure
3	RT. STA. 768 + 90 TO 771 + 6	Silver Creek Structure
4	RT. STA. 912 + 73 TO 915 + 30	Leaf River Structure
4	LT. STA. 913 + 4 TO 915 + 61	Leaf River Structure
18	TOTAL	

78300100 PAVEMENT MARKING REMOVAL

SO. FT.	LOCATION	REMARK'S
61	LT. STA. 720 + 40 TO 722 + 22	Mud Creek Bridge (Edge Line)
61	RT. STA. 720 + 40 TO 722 + 22	Mud Creek Bridge (Edge Line)
121	CL 720 + 40 TO 722 + 22	Mud Creek Bridge (Median/Double Yellow)
52	LT. STA. 769 + 20 TO 770 + 76	Silver Creek Bridge (Edge Line)
52	RT. STA. 769 + 20 TO 770 + 76	Silver Creek Bridge (Edge Line)
104	CL 769 + 20 TO 770 + 76	Silver Creek Bridge (Edge Line)
111	LT. STA. 912 + 57 TO 915 + 89	Leaf River Bridge (Edge Line)
111	RT. STA. 912 + 57 TO 915 + 89	Leaf River Bridge (Edge Line)
221	CL 912 + 57 TO 915 + 89	Leaf River Bridge (Edge Line)
145	CL 1188 + 62 TO 1190 + 80	IL 72 - Double Yellow - STAGE 1
74	RT. STA. 1190 + 15 TO 1192 + 38	IL 72 - Edge Line - STAGE 1
216	RT. STA. 1064 + 25 TO 1070 + 74	IL 2 - Edge Line - STAGE 1
118	CL 1070 + 65 TO 1072 + 42	IL 2 - Double Yellow - STAGE 1
147	LT. STA. 1068 + 0 TO 1072 + 42	IL 2 - Edge Line - STAGE 2
1595	TOTAL	

Z0020900 ESTABLISHING AND REFERENCING LAND SECTION MARKERS

EACH	LOCATION	REMARK'S
1	RT. STA. 740 + 0 +/-	Witness Point (N1964646.6211, E723058.3542)
1	RT. STA. 930 + 52.18	Concrete Monument (N1980676.2930, E730730.3164)
2	TOTAL	

Z0023600 FILLING EXISTING CULVERTS

EACH	LOCATION	REMARK'S
1	LT/RT 895 + 46	2x2 Concrete Box Culvert
4	680 + 0 TO 1068 + 0	As determined by the Resident Engineer (If needed) (as replacement to removal of existing structures)
5	TOTAL	

Z0025500 FURNISHING AND INSTALLING PROPERTY MARKERS

EACH	LOCATION	REMARK'S
37	R.O.W. Areas	
7	Easement Areas	
6	Contingency Item	
50	TOTAL	As determined by the Resident Engineer (If needed)

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARK'S
1	LT. STA. 1190 + 50	IL 72 - STAGE 1
1	LT. STA. 1070 + 74	IL 2 - STAGE 1
2	TOTAL	

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARK'S
1	RT. STA. 1190 + 17	IL 72 - STAGE 1
1	RT. STA. 1070 + 72	IL 2 - STAGE 1
2	TOTAL	

Z0055100 RUMBLE RESURFACING

SO. YD	LOCATION	REMARK'S
37.5	-104 + 0 TO -79 + 0	Mudd Creek Rd. (200' prior to Stop Ahead Sign)
37.5	4 + 46 TO 4 + 71	Mudd Creek Rd. (500' prior to Stop Bar)
37.5	6 + 46 TO 6 + 71	Mudd Creek Rd. (300' prior to Stop Bar)
36.7	1181 + 13 TO 1181 + 38	IL 72
33.3	1188 + 0 TO 1188 + 25	IL 72
34.2	1190 + 0 TO 1190 + 25	IL 72
216.7	TOTAL	