

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TOTAL BILL OF MATERIALS

DESCRIPTION	UNIT	QTY.
Removal and Disposal of Unsuitable Material for Structures	Cu. Yd.	120
Stone Riprap, Class A6	Sq. Yd.	164
Filter Fabric	Sq. Yd.	227
Removal of Existing Structure No. 9	Each	1
Reinforcement Bars	Pound	24,050
Name Plates	Each	1
Concrete Box Culverts	Cu. Yd.	160.0
Breaker-Run Crushed Stone	Ton	300

GENERAL NOTES

Construction to be completed under detour.

Precast alternate not allowed.

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.

Layout of the slope protection system may be varied to suit ground conditions in the field as directed by the engineer.

A distance of one half the length of the wingwall but not less than six feet of the barrel shall be poured monolithically with the wingwalls.

DESIGNED <i>KJB</i>
CHECKED <i>CTH</i>
DRAWN <i>KJB</i>
CHECKED <i>DFM</i>

GENERAL NOTES & TOTAL BILL OF MATERIALS
STRUCTURE NO. 071-1135

SHEET NO. 2	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	742	37 R-4	OGLE	867	192
5 SHEETS	CONTRACT NO. 64E17				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT					