SUMMARY OF QUANTITIES

CODE NO.	ITEM	100% STATE SAFETY-2A TAZEWELL COUNTY, URBAN			
		UNIT	TOTAL	MCHD	CONTRACT MAINT.
50102400	CONCRETE REMOVAL	CUYD	0.5	0.5	
50300255	CONCRETE SUPERSTRUCTURE	CUYD	0.5	0.5	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6130	6130	
50501110	STRUCTURAL STEEL REMOVAL	POUND	5640	5640	
50501130	STRUCTURAL STEEL REPAIR	POUND	1500		1500
67100100	MOBILIZATION	LSUM	1	0.5	0.5
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	LSUM	1	0.5	0.5
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	LSUM	1	1	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1400	1400	
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	467	467	
* 78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	2392	2392	
78300100	PAVEMENT MARKING REMOVAL	SQFT	800	800	
X0323583	SPEED INDICATOR SIGN	CAL DA	70	45	25
Z0003600	BEAM STRAIGHTENING	LSUM	1	0.5	0.5
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1	
Z0073300	TEMPORARY SHORING AND CRIBBING	LSUM	1	1	
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	LSUM	1	1	

*SPECIALTY ITEM

SN. 090-0091 PINECREST DRIVE OVER I-74

S:-GEN-DRAFT-STD&PLNS-SQUAD14-BRIDGE CONTRACTS-STEEL BEAM REP-68976 SN090-0091-SN.090-0091 PinecrestDr.ovr1-74.dgn

FILE NAME = SN.090-0091 Straighten&Strengthen.dgn	USER NAME = jonesce	DESIGNED - CEJ	REVISED - ___
		DRAWN - CEJ	REVISED - ___
	PLOT SCALE = 103.7051 ' / IN.	CHECKED - ---	REVISED - ___
	PLOT DATE = 5/18/2010	DATE - 05/13/2010	REVISED - ___

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ | SHEET NO. __ OF ___ SHEETS | STA. _____ TO STA. _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(90-14HB-1(BR))I	TAZEWELL	17	3
STEEL BEAMS REP./REPL.		CONTRACT NO. 68976		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		