

CODE NO.	ITEM	UNIT	CONSTRUCTION CODE: 1000 FUNDING: 100% STATE			
			URBAN	FAP 658	FAP 662	FAP 666
			TOTAL	SECTION "A" OLD IL 29	SECTION "B" IL 4	SECTION "C" PEORIA RD
44213000	PATCHING REINFORCEMENT	SQ YD	181		181	-
44213100	PAVEMENT FABRIC	SQ YD	780	780	-	-
44213200	SAW CUTS	FOOT	3,746	3,150	596	-
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,180	-	1,180	-
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	866	-	866	-
48203100	HOT-MIX ASPHALT SHOULDERS	TON	6134	1,330	4,338	466
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	546	-	546	-
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15"	FOOT	98	-	98	-
550A0090	STORM SEWERS, CLASS A, TYPE 1, 18"	FOOT	12	-	12	-
55100500	STORM SEWER REMOVAL, 12"	FOOT	191	-	191	-
60219500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15, FRAME AND LID	EACH	12	-	12	-
60220005	MANHOLES, TYPE A, 4'-DIAMETER, WITH MEDIAN INLET (604101)	EACH	1	-	1	-
60237010	INLETS, TYPE A, TYPE 15, FRAME AND LID (24" DEPTH)	EACH	9	-	9	-
60255500	MANHOLES TO BE ADJUSTED	EACH	31	30	-	1
60260100	INLETS TO BE ADJUSTED	EACH	5	-	5	-
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	35	35	-	-
60500060	REMOVING INLETS	EACH	11	-	11	-
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	9	-	9	-
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	224	-	224	-
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	145	-	145	-
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	176	-	176	-
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1,291	-	1,291	-
60622320	CONCRETE MEDIAN, TYPE SM-4.24	SQ FT	108	-	108	-
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	4	4	4

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 658	SECTION *	COUNTY SANGAMON	TOTAL SHEETS 206	SHEET NO. 6
et:\pwwork\pwwidgt\LAUGHLINR1\dms47710\672C35-sht-500.dgn	PLOT SCALE = 40.0000' / 1"	DRAWN -	REVISED -		SCALE:	SHEET NO. 3	OF 6 SHEETS	STA.	TO STA.	CONTRACT NO. 72C35			
	PLOT DATE = Apr-30-2010 09:13:03AM	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE -	REVISED -		Rev.								