

CODE NO.	ITEM	UNIT	CONSTRUCTION CODE: 1000 FUNDING: 100% STATE			
			URBAN	FAP 658	FAP 662	FAP 666
			TOTAL	SECTION "A" OLD IL 29	SECTION "B" IL-4	SECTION "C" PEORIA RD.
67100100	MOBILIZATION	L SUM	1	0.33	0.34	0.33
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.33	0.34	0.33
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	0.33	0.34	0.33
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.33	0.34	0.33
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.33	0.34	0.33
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.33	0.34	0.33
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	7	7	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	4	4	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	22,606	10,460	8,573	3,573
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,056	1,743	831	482
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	36	18	18	--
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	27,016	17,310	--	9,706
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	6,126	1,516	4,610	--
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,153	1,088	1,065	--
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	2,581	821	1,250	510
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B INLAID - LINE 5"	FOOT	15,997	7,403	5,378	3,216
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B INLAID - LINE 6"	FOOT	11,434	6,368	4,749	317
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B INLAID - LINE 8"	FOOT	121	121	--	--
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B INLAID - LINE 24"	FOOT	1,841	1,003	614	224
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,260	454	476	330
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,260	454	476	330
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	86	43	43	--
* 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	17	--	17	--
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	10	5	5	--
* 81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	28	14	14	--
* 81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	120	60	60	--

* SPECIALTY ITEM

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\VPWIDOT\LAUHL\INR\dm47710\0572C35-shr-500.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO. 4 OF 6 SHEETS	STA.	TO STA.	658	*	SANGAMON	206	7
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISED -								CONTRACT NO. 72C35		
PLOT DATE = Apr-30-2010 09:13:11AM		DATE -	REVISED -								ILLINOIS FED. AID PROJECT		