

SECTION "B" -- IL 4/VETERANS PKWY RESURFACING SCHEDULE																		
DESCRIPTION	STATION TO STATION	LENGTH	AVG. PAVT. WIDTH	PAVMENT AREA	EOP HMA SHLDR WIDTH	MEDIAN HMA SHLDR WIDTH	HMA SHLDR AREA	BIT MAT PRIMECOAT	AGG PRIMECOAT	LEVEL BINDER	2" POLY HMA SURFACE	HMA SURF. REM 2"	2" HMA SHLDR	AGG SHLDR	GRADE & SHAPE SHLDR	BUTT JOINT	TEMP RAMPS	
		(FT)	(FT)	(SQYD)	(FT)	(FT)	(SQYD)	(TON)	(TON)	(TON)	(TON)	(SQYD)	(TON)	(TON)	(UNIT)	(SQYD)	(SQYD)	
SIDE ROAD -- 100 W. ROAD																		
MAIN LINE	+20 +88	68	45	340	--	--	--	0.3	0.7	--	38	318	--	--	--	22.2	14.8	
MAIN LINE	8+75 9+17	42	45	210	--	--	--	0.2	0.4	--	24	188	--	--	--	22.2	14.8	
SIDE ROAD -- BROWNING ROAD																		
MAIN LINE	16+85 17+89	104	43	491	--	--	--	0.2	1.0	--	55	447	--	--	--	44.4	29.6	
SB RT TURN	16+85 17+67	82	26	231	--	--	--	0.1	0.5	--	26	231	--	--	--			
WB RT TURN	16+85 17+92	107	18	210	--	--	--	0.1	0.4	--	24	210	--	--	--			
MAIN LINE	19+10 20+27	117	43	553	--	--	--	0.2	1.1	--	62	508	--	--	--	44.4	29.6	
EB RT TURN	19+12 20+27	115	25	319	--	--	--	0.1	0.6	--	36	319	--	--	--			
NB RT TURN	19+40 20+05	65	24	173	--	--	--	0.1	0.3	--	19	173	--	--	--			
SIDE ROAD -- 8TH STREET																		
MAIN LINE	47+65 48+97	132	24	352	--	--	--	0.1	0.7	--	39	293	--	--	--	58.9	39.3	
SB RT TURN	47+65 48+97	132	26	379	--	--	--	0.1	0.8	--	42	379	--	--	--			
EB RT TURN	47+65 49+15	150	18	407	--	--	--	0.2	0.8	--	46	407	--	--	--			
MAIN LINE	50+20 51+65	145	32	508	--	--	--	0.2	1.0	--	57	480	--	--	--	27.8	18.5	
NB RT TURN	50+30 51+10	80	32	276	--	--	--	0.1	0.6	--	31	276	--	--	--			
WB RT TURN	50+17 51+25	108	20	239	--	--	--	0.1	0.5	--	27	239	--	--	--			
SIDE ROAD TOTALS				4,687				2.0	9.4	--	525	4,467	--	--	--	220	147	
NORTHBOUND TOTALS				30,172			16,846	18.0	93.6	75	3,379	46,858	1,887	498	180	240	58	
SOUTHBOUND TOTALS				28,156			16,418	17.8	89.1	75	3,153	44,414	1,839	514	183	240	58	
JOB TOTALS		9077		63,015			33,264	38	192	149	7,058	95,739	3,726	1,012	363	700	262	

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et\pw\work\PWIDOT\LAUGHLINR1\dms47710\072035-ahtr-schedule.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES SECTION "B" IL 4			
SCALE:	SHEET NO. 2A OF 7 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658		SANGAMON	206	28A
			CONTRACT NO. 72C35	
ILLINOIS FED. AID PROJECT				