SECTION "C" PEORIA RD. RESURFACING SCHEDULE

DESCRIPTION	STATION TO STATION		LENGTH (FT)	AVG. PAVT WIDTH (FT)	PAVEMENT AREA (SQ YD)	EOP SHLDR WIDTH (FT)	MED SHLDR WIDTH (FT)	SHLDR AREA (SQ YD)	BIT MAT PRIMECOAT (TON)	AGG PRIMECOAT (TON)	1.5" HMA SURFACE (TON)	2.0" POLYMER HMA SURFACE (TON)	2.5" HMA SURF. REM (SQ YD)	2" HMA SURF. REM (SQ YD)	1" LEVELING BINDER (TON)	HMA SHLDR (TON)	Butt Joint (SQYD)	Temp Ramps (SQYD)
NORTHBOUND LANES																		
MAIN LINE	52+40	52+50	10.00	30	33	--	--	--	0.1	0.1	3	--	33	--	2	--	100	22
MAIN LINE	52+50	52+55	5.00	30	17	--	--	--	0.1	0.1	1	--	17	--	1	--	--	--
MAIN LINE	52+55	78+45	2,590.12	32	9,209	--	--	--	3.5	18.4	774	--	9,209	--	516	--	--	--
STA. EQN 78+45.12(BK) = 1+56.70(AH)																		
MAIN LINE	1+57	14+50	1,293.30	32	4,598	--	--	--	1.7	9.2	386	--	4,598	4,598	258	--	--	--
MAIN LINE	14+50	15+17	67.25	29.5	220	--	--	--	0.1	0.4	--	25	--	220	--	--	--	--
STA. EQN 15+17.25(BK) = 144+00.00(AH)																		
MAIN LINE	144+00	151+34	734.00	28	2,284	--	--	--	0.9	4.6	--	256	--	2,284	--	--	--	--
MAIN LINE	498+40	499+12	72.00	39	312	10	7	136	0.1	0.6	--	35	--	312	--		--	--
MAIN LINE	499+12	500+86	174.41	28	543	10	7	329	0.2	1.1	--	61	--	543	--	37	--	--
MAIN LINE	500+86	504+67	380.59	27.5	1,163	10	8	761	0.4	2.3	--	130	--	1,163	--	85	--	--
MAIN LINE	504+67	505+84	117.00	28	364	10	--	130	0.1	0.7	--	41	--	364	--	15	--	--
MAIN LINE	505+84	508+44	260.00	28	809	10	--	289	0.3	1.6	--	91	--	809	--	32	--	--
MAIN LINE	508+44	512+74	430.00	28	1,338	10	2	573	0.5	2.7	--	150	--	1,338	--	64	--	--
MAIN LINE	512+74	512+84	10.00	28.5	32	--	1	1	0.1	0.1	--	4	--	32	--	0.1	95	21
PEORIA RD. / IL 4/VETERANS AVE. TURN LANES																		
LEFT TURN	151+34	152+72	138	10	153	--	--	--	0.1	0.3	--	17	--	153	--	--	--	--
LEFT TURN	152+72	156+06	334	16	594	--	--	--	0.2	1.2	--	67	--	594	--	--	--	--
RIGHT TURN	151+34	156+06	472	16	839	--	--	--	0.3	1.7	--	94	--	839	--	--	--	--
RIGHT TURN	151+34	156+06	472	16	839	--	--	--	0.3	1.7	--	94	--	839	--	--	--	--
PEORIA RD. / WATERWORKS RD. TURN LANES																		
LEFT TURN	504+10	505+84	174	11	213	2	0	39	0.1	0.1	--	24	--	213	--	4	--	--
LEFT TURN	505+84	507+93	209	18	418	2	3.8	135	0.2	0.1	--	47	--	418	--	15	--	--
NORTHBOUND TOTALS					**23,978**	**64**	**29**	**2,393**	**9**	**47**	**1,164**	**1,133**	**13,858**	**14,719**	**776**	**253**	**195**	**43**