

SECTION "C" PEORIA RD. RESURFACING SCHEDULE																		
DESCRIPTION	STATION TO STATION	LENGTH	AVG. PAVT WIDTH	PAVEMENT AREA	EOP SHLDR WIDTH	MED SHLDR WIDTH	SHLDR AREA	BIT MAT PRIMECOAT	AGG PRIMECOAT	1.5" HMA SURFACE	2.0" POLYMER HMA SURFACE	2.5" HMA SURF. REM	2.0" HMA SURF. REM	LEVELING BINDER	HMA SHLDR	Butt Joint	Temp Ramps	
		(FT)	(FT)	(SQYD)	(FT)	(FT)	(SQYD)	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(TON)	(SQYD)	(SQYD)	
COLORPLANT RD RESURFACING																		
SOUTHBOUND LANES																		
MAIN LINE	310+12	311+34	122	16	217	--	--	0.1	0.4	--	24	--	217	--	--	53	13	
NORTHBOUND LANES																		
MAIN LINE	310+12	311+44	132	18	264	--	--	0.1	0.5	--	30	--	264	--	--	60	13	
PEORIA RD. / COLORPLANT RD TURN LANES																		
RIGHT TURN	310+12	311+44	158	20	351	--	--	0.1	0.7	--	39	--	351	--	--	--	--	
MAINLINE TOTALS					50,317	112	51	4,336	20	101	2,322	2,540	13,978	41,057	1,548	466	502	112

SIDEROAD & ENTRANCE IMPROVEMENT													
DESCRIPTION	STATION	EOP WIDTH	ENTRANCE WIDTH	LENGTH EOP TO LIMITS	PAVEMENT AREA	PREP OF BASE	HMA REM. BUTT JOINT	BIT MATLS PRIMECOAT	AGG PRIMECOAT	INCIDENTAL BIT SURF	2.5" HMA SURF. REM	LEVELING BINDER	1.5" HMA SURFACE
		(FT)	(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(TON)	(TON)
TAFT ST.	54+53	60	26	35	167.2	167	57.8	0.1	0.3	23	--	--	--
SAUNDERS ST.	62+40	62	25	40	193	193	55.6	0.1	0.4	27	--	--	--
WARREN ST.	67+00	65	30	40	211	211	66.7	0.1	0.4	30	--	--	--
TAINTOR RD. (WEST)	14+13	160	29	125	1,313	--	64.4	0.5	3.3	--	1,312	74	184
TAINTOR RD. (EAST)	14+13	80	26	60	353	353	57.8	0.1	0.7	49	--	--	--
EVERGREEN PARK	407+40	70	20	40	200	200	44.4	0.1	0.4	28	--	--	--
WATERWORKS RD.	407+40	65	28	40	207	207	62.2	0.1	0.4	29	--	--	--
SIDEROAD TOTALS					2644	1332	409	1	6	186	1312	73	184

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES SECTION "C" (PEORIA RD.)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
or:\pw\work\PIWDOT\LAUGHLINR1\dms47710\72C35-shr-schedule.dgn	DRAWN -	REVISED -	658			*	SANGAMON	206	36	
PLOT SCALE = 48.0000' / 1" IN.	CHECKED -	REVISED -	CONTRACT NO. 72C35							
PLOT DATE = Apr-30-2010 11:14:32AM	DATE -	REVISED -	SCALE:			SHEET NO. 3 OF 3 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		