


NOTES:

SHOULDER SLOPE FOR SUPERELEVATION

- (A) LOW SIDE: SLOPE SHALL BE SAME AS SUPERELEVATION, BUT NOT LESS THAN 4.0%.
- (B) HIGH SIDE: WHEN SUPERELEVATION IS BETWEEN 0% AND 4%, SLOPE SHOULDER @ 4.0%. WHEN SUPERELEVATION EXCEEDS 4.0%, THE SHOULDER SHALL BE SLOPED SO THAT THE ALGEBRAIC DIFFERENCE BETWEEN PAVEMENT AND SHOULDER WILL NOT BE GREATER THAN 8.0%.


TURN LANE SLOPE FOR SUPERELEVATION

- (C) LOW SIDE: SLOPE SHALL BE SAME AS SUPERELEVATION.



RIGHT & LEFT LANES
 STA. 257+22.60 - 261+55.48
 STA. 265+98.64 - 270+27.21
 STA. 491+98.51 - 494+93.49 (NBL)
 STA. 391+83.78 - 394+68.75 (SBL)

- (1) EXISTING HOT-MIX ASPHALT SHOULDERS
- (2) EXISTING HOT-MIX ASPHALT SHOULDERS WITH STD. 2438 RUMBLE STRIPS, CONTINUOUS
- (3) EXISTING PCC PAVEMENT (8")
- (4) EXISTING STABILIZED SUB-BASE (4")
- (5) EXISTING SUB-BASE GRANULAR MATERIAL, TY C
- (6) EXISTING CONCRETE CURB & GUTTER
- (6A) EXISTING CONCRETE CURB & GUTTER M-2.12 OR M-4.12
- (6B) EXISTING CONCRETE CURB & GUTTER M-2.24 OR M-4.24
- (7) EXISTING AGGREGATE SHOULDERS, TY B
- (8) EXISTING CONCRETE MEDIAN (4" OR 6")
- (9) EXISTING SOLID MEDIAN, STD. 2122
- (10) EXISTING BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH), 13.5"
- (11) PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL (2")
- (12) PROPOSED HOT-MIX ASPHALT SURFACE COURSE, POLYMER MIX "D", N70-2"
- (13) PROPOSED HOT-MIX ASPHALT SHOULDERS (2")
- (14) PROPOSED HOT-MIX ASPHALT SHOULDERS WITH STD. 2438 RUMBLE STRIPS, CONTINUOUS
- (15) PROPOSED PAVEMENT MARKING, LINE (5")
- (16) PROPOSED AGGREGATE SHOULDERS, TYPE B
- (17) PROPOSED SUB-BASE GRANULAR MATERIAL, TYPE A, 8"
- (18) PROPOSED COMBINED CONCRET E CURB & GUTTER, TYPE M 4.24
- (19) PROPOSED HOT-MIX ASPHALT BASE COURSE, 11"
- (20) PROPOSED LEVELING BINDER (MACHINE METHOD), 1" & VAR. DEPTH
- (21) PROPOSED HOT-MIX ASPHALT SURFACE COURSE, 1.5"
- (22) PROPOSED HOT-MIX ASPHALT SHOULDERS, 8"
- (23) PROPOSED SUB-BASE GRANULAR MATERIAL, TYPE B, VAR. DEPTH
- (24) PROPOSED CONCRETE MEDIAN SURFACE, 4"



SUPERELEVATION & SUPERELEVATION TRANSITION
 STA. 253+50.00 - 257+22.60
 STA. 270+27.21 - 280+20.75
 STA. 384+81.97 - 391+83.78 (SBL)
 STA. 486+41.00 - 491+98.51 (NBL)

STATION EQUATION:
 STA. 255+48.03 (BK) = STA. 255+42.57 (AH)

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS, SECTION "B" (IL 4), VETERANS PKWY		F.A.P. RTE. =	SECTION =	COUNTY =	TOTAL SHEETS =	SHEET NO. =	
er:\pwwork\pwwid\T.LAUGHLINR1\dms4710\c\72035-sh-t-typicals-veterans.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO. 9 OF 10 SHEETS	STA. TO STA.	658		SANGAMON	206	56
		CHECKED -	REVISED -									
		DATE -	REVISED -									