



EXIST. CURVE 13
 PI STA. = 267+36.92
 $\Delta = 34^\circ 00' 00''$ (RT)
 $D = 1^\circ 28' 00''$
 $R = 3,906.54'$
 $T = 1,194.35'$
 $L = 2,318.19'$
 $E = 178.50'$
 $e = 3.6\%$
 $T.R. = 66.67'$
 $S.E. RUN = 160'$
 $P.C. STA. = 255+42.57$
 $P.T. STA. = 278+60.76$

LEGEND

- | | |
|----------------------------|---|
| ① URETHANE- 5" YELLOW | ⑨ THERMOPLASTIC- 12" YELLOW |
| ② URETHANE- 5" WHITE | ⑩ THERMOPLASTIC- 12" WHITE |
| ③ URETHANE- 8" WHITE | ⑪ PREFORMED PLASTIC TYPE B- INLAID- LETTERS AND SYMBOLS |
| ④ URETHANE- 12" YELLOW | ⑫ PREFORMED PLASTIC TYPE B- INLAID - 5" YELLOW |
| ⑤ URETHANE-12" WHITE | ⑬ PREFORMED PLASTIC TYPE B- INLAID - 5" WHITE |
| ⑥ THERMOPLASTIC- 5" YELLOW | ⑭ PREFORMED PLASTIC TYPE B- INLAID - 6" WHITE |
| ⑦ THERMOPLASTIC- 5" WHITE | ⑮ PREFORMED PLASTIC TYPE B- INLAID - 24" WHITE |
| ⑧ THERMOPLASTIC- 8" WHITE | |

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN VIEW - SECTION "B" (IL 4 /VETERANS PKWY)	F.A.P. RTE. 658	SECTION •	COUNTY SANGAMON	TOTAL SHEETS 206	SHEET NO. 98		
ei:\pwork\pwork\WIDOT\LAUGHLINRL\dms47718\72C35-shp\enr14.dgn		DRAWN -	REVISED -			SCALE: SHEET NO. 14 OF 20 SHEETS STA. TO STA.		CONTRACT NO. 72C35				
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT						
PLOT DATE = Apr-30-2010 02:33:34PM		DATE -	REVISED -			• 1-1(RS,TS-1)27RS-679Z&102RS-4						