

PAVEMENT PATCHING					
LOCATION	PATCH SIZE (FT X FT)	PATCH DEPTH (INCH)	PATCH SIZE (SQ YD)	PATCH TYPE (I, II, III, IV)	PATCH CLASS (A, B, C, OR D)
IL 16 / IL 127 (WOOD ST. TO JUNCTION OF IL 16 / IL 127)					
NO PATCHING					
IL 16 (JUNCTION OF IL 16 / IL 127 TO INDUSTRIAL PARK DRIVE)					
EASTBOUND LANE, EDGE OF PAVEMENT	200 X 4	12	88.9	IV	*
EASTBOUND LANE, EDGE OF PAVEMENT	6 X 40	12	26.7	IV	*
EAST BOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	15 X 6	12	9.0	II	*
WESTBOUND LANE	8 X 12	12	10.7	II	*
WESTBOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
WESTBOUND LANE	12 X 12	12	16.0	III	*
WESTBOUND LANE	20 X 12	12	26.7	IV	*
BRIDGE					
WESTBOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	12 X 6	12	8.0	II	*
PRESTON STREET					
EASTBOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
WESTBOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
WESTBOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
WESTBOUND LANE	6 X 12	12	8.0	II	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
WESTBOUND LANE	12 X 6	12	8.0	II	*
WESTBOUND LANE	12 X 6	12	8.0	II	*
WESTBOUND LANE	6 X 6	12	4.0	I	*
WESTBOUND LANE	6 X 6	12	4.0	I	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
WESTBOUND LANE	6 X 6	12	4.0	I	*
EASTBOUND LANE	10 X 12	12	13.3	II	*
WESTBOUND LANE	8 X 12	12	10.7	II	*
EASTBOUND LANE	6 X 12	12	8.0	II	*
WESTBOUND LANE	4 X 6	12	2.7	I	*
IL 16 (INDUSTRIAL PARK DRIVE TO ± 500' EAST OF VIADUCT)					
EASTBOUND LANE	6 X 6	10	4.0	I	C
EASTBOUND LANE	6 X 12	10	8.0	II	C
WESTBOUND LANE	6 X 12	10	8.0	II	C
EASTBOUND LANE	6 X 12	10	8.0	II	C
EASTBOUND LANE	6 X 12	10	8.0	II	C
WESTBOUND LANE	6 X 12	10	8.0	II	C
EASTBOUND LANE	6 X 12	10	8.0	II	C
EASTBOUND LANE	6 X 12	10	8.0	II	C
IL 127 (JUNCT. OF IL 16 / IL 127 TO ±500' NORTH OF R.R. OVERPASS)					
SOUTHBOUND LANE	4 X 12	15	5.3	II	*
SOUTHBOUND LANE	4 X 12	15	5.3	II	*
SOUTHBOUND TURN LANE	4 X 12	15	5.3	II	*
SOUTHBOUND LANE	8 X 4	15	3.6	I	*
SOUTHBOUND LANE	4 X 6	15	2.7	I	*
NORTHBOUND LANE (WITH WATER VALVE)	4 X 4	15	1.8	I	*
SOUTHBOUND LANE	4 X 12	15	5.3	II	*
NORTHBOUND LANE (WITH WATER VALVE)	4 X 12	15	5.3	II	*
GRAND TOTALS =			463.3 SQ YD		

* - CONTRACTORS OPTION (CLASS C OR D)

PATCHING PAY ITEM QUANTITIES:	
CLASS C PATCHES, TYPE I, 10"	= 4.0 SQ YD
CLASS C PATCHES, TYPE II, 10"	= 56.0 SQ YD
PAVEMENT PATCHING TYPE I, 12"	= 14.7 SQ YD
PAVEMENT PATCHING TYPE I, 15"	= 8.1 SQ YD
PAVEMENT PATCHING TYPE II, 12"	= 195.7 SQ YD
PAVEMENT PATCHING TYPE II, 15"	= 26.5 SQ YD
PAVEMENT PATCHING TYPE III, 12"	= 16.0 SQ YD
PAVEMENT PATCHING TYPE IV, 12"	= 142.3 SQ YD
TOTAL PATCHING	= 463.3 SQ YD

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	MARKER REMOVAL (EACH)
IL RTE. 16 / IL RTE. 127	68
IL RTE. 16	67
IL RTE. 127	266
TOTALS = 401 EACH	

FILE NAME =	USER NAME = laughlinr1	DESIGNED - RTS	REVISED -
c:\pwork\pwork\DOT\LAUGHLINRL\d0105356\72C52-eh-sched.dgn		DRAWN - RTS	REVISED -
		CHECKED - RTS	REVISED -
		DATE - 3-10-10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES			
SCALE:	SHEET NO. 1 OF 8 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	MONTGOMERY	60	14
CONTRACT NO. 72C52				
ILLINOIS FED. AID PROJECT				

*-20RS-7, 21RS-6, 104RS, 105RS-4
**-325, 42