

HOT-MIX ASPHALT SURFACE REMOVAL, 2" (FOR MAINLINE IL 16/127, IL 16, & IL 127)		
LOCATION (STATION TO STATION)	SURFACE AREA (BY CADD) (SQUARE FOOT)	SURFACE AREA (SQUARE YARD)
<b>IL RTE. 16 / IL RTE. 127</b>		
27+86.08 TO 28+81.79	2,549.2	283.2
28+81.79 TO 33+00.00	11,328.5	1,258.7
33+00.00 TO 34+42.93	7,370.2	818.9
34+42.93 TO 36+08.04	8,003.6	889.3
38+19.85 TO 10+82.02 (MAIN ST.)	9,069.2	1,007.7
38+19.85 TO 40+46.77	9,002.6	1,000.3
40+46.77 TO 41+51.70	4,578.8	508.8
<b>SUB-TOTALS =</b>	<b>51,902.1</b>	<b>5,766.9</b>
<b>IL RTE. 16</b>		
43+84.77 TO 44+86.08	6,254.3	694.9
44+86.08 TO 47+00.00	7,195.6	799.5
47+00.00 TO 50+00.00	8,989.5	998.8
<b>STATION EQUATION:</b>		
50+00.00 (BK.) = 00+00.00 (AHD.)		
00+00.00 TO 02+50.00	7,197.0	799.7
02+50.00 TO 08+00.00	16,061.0	1,784.6
08+00.00 TO 9+84.08	5,437.2	604.1
<b>BRIDGE OMISSION:</b>		
9+84.08 TO 10+83.69		
10+83.69 TO 13+50.00	7,796.4	866.3
13+50.00 TO 19+00.00	16,017.5	1,779.7
19+00.00 TO 24+50.00	16,249.9	1,805.5
24+50.00 TO 30+00.00	16,045.7	1,782.9
30+00.00 TO 35+50.00	16,040.0	1,782.2
35+50.00 TO 41+00.00	16,156.8	1,795.2
41+00.00 TO 44+57.00	10,492.6	1,165.8
<b>SUB-TOTALS =</b>	<b>149,933.6</b>	<b>16,659.3</b>
<b>IL RTE. 127</b>		
00+00.00 TO 00+75.00	3,469.9	385.5
00+75.00 TO 06+50.00	23,337.0	2,593.0
06+50.00 TO 12+00.00	20,210.6	2,245.6
12+00.00 TO 17+50.00	20,907.4	2,323.0
17+50.00 TO 23+00.00	20,213.5	2,245.9
23+00.00 TO 28+50.00	20,223.3	2,247.0
28+50.00 TO 34+00.00	20,160.8	2,240.1
34+00.00 TO 39+50.00	20,210.5	2,245.6
39+50.00 TO 45+00.00	20,213.3	2,245.9
45+00.00 TO 50+50.00	20,179.3	2,242.1
50+50.00 TO 56+00.00	22,512.8	2,501.4
56+00.00 TO 58+08.91	7,298.7	811.0
<b>SUB-TOTALS =</b>	<b>218,937.1</b>	<b>24,326.3</b>
<b>PARKING LANES</b>		
ALONG IL RTE. 127 & MAIN ST.	3,315.5	368.4
ALONG IL RTE. 127	2,072.0	230.2
<b>SUB-TOTALS =</b>	<b>5,387.4</b>	<b>598.6</b>
<b>GRAND TOTALS =</b>	<b>426,160.2 SQ FT</b>	<b>47,351.2 SQ YD</b>

HOT-MIX ASPHALT SURFACE REMOVAL, 2" (FOR SIDEROADS)		
LOCATION (STATION TO STATION)	SURFACE AREA (BY CADD) (SQUARE FOOT)	SURFACE AREA FOR REMOVAL (SQUARE YARD)
<b>IL RTE. 16 / IL RTE. 127</b>		
WOOD ST. (EAST)	937.6	104.2
WOOD ST. (WEST)	812.2	90.3
TILSON STREET	1,411.9	156.9
MILL STREET	682.5	75.8
PLEASANT STREET	610.4	67.8
<b>SUB-TOTALS =</b>	<b>4,454.6</b>	<b>495.0</b>
<b>IL RTE. 16</b>		
PRESTON STREET	637.7	74.9
ECCLES STREET (SOUTH)	778.4	86.5
ANNA STREET	834.8	92.8
<b>SUB-TOTALS =</b>	<b>2,286.9</b>	<b>254.1</b>
<b>IL RTE. 127</b>		
EAST TREMONT STREET	1,485.9	165.1
WEST TREMONT STREET	1,075.0	119.4
SUMMER STREET (EAST)	1,293.6	143.7
SUMMER STREET (WEST)	1,291.8	143.5
JEFFERSON LANE	859.6	95.5
EAST FAIRGROUNDS AVENUE	2,598.7	288.7
WEST FAIRGROUNDS AVENUE	2,736.1	304.0
VANDALIA STREET	1,201.2	133.5
ROUNTREE STREET	2,314.2	257.1
EAST MECHANIC STREET	2,320.4	257.8
HILLTOP ROAD	986.1	109.6
IDA STREET (10' APPRON)	644.0	71.6
HUBER STREET (10' APPRON)	665.3	73.9
FIRST STREET	1,508.5	167.6
EAST WILLOW AVENUE (10' APPRON)	2,590.8	287.9
SENATOR MILLER DRIVE (10' APPRON)	3,136.9	348.9
<b>SUB-TOTALS =</b>	<b>26,708.1</b>	<b>2,967.6</b>
<b>GRAND TOTALS =</b>	<b>33,449.6 SQ FT</b>	<b>3,716.7 SQ YD</b>

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (FOR SIDEROADS)		
LOCATION	SURFACE AREA (BY CADD) (SQUARE FOOT)	SURFACE AREA FOR REMOVAL (SQUARE YARD)
<b>IL RTE. 16</b>		
ROUNTREE STREET (NORTH)	996.1	110.7
ROUNTREE STREET (SOUTH)	899.0	99.9
CHASE STREET	867.6	96.4
LAKEVIEW DRIVE	216.0	24.0
LEVA STREET (10' APPRON)	783.9	87.1
VIRGINIA STREET (NORTH)	265.2	29.5
VIRGINIA STREET (SOUTH)	836.1	92.9
ALLEY	97.8	10.9
PARK STREET	1,018.8	113.2
CENTRE STREET	861.1	95.7
<b>TOTALS =</b>	<b>6,841.6 SQ FT</b>	<b>760.2 SQ YD</b>

FILE NAME =	USER NAME = laughlinr1	DESIGNED - RTS	REVISED -
c:\pwork\p1000\LAUGHLINR1\0105356\	72052-shr-schedule.dgn	DRAWN - RTS	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - RTS	REVISED -
	PLOT DATE = Mar-26-2010 11:59:15AM	DATE - 3-10-10	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES			
SCALE:	SHEET NO. 2 OF 8 SHEETS	STA.	TO STA.

*-20RS-7, 21RS-6, 104RS, 105RS-4 **-325, 42				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	.	MONTGOMERY	60	15
CONTRACT NO. 72052			ILLINOIS FED. AID PROJECT	