

THERMOPLASTIC PAVEMENT MARKING - LINE 5"		
LOCATION (STATION)	DESCRIPTION	QUANTITY (FOOT)
IL RT. 16 / IL RTE. 127		
27+86.08 TO 28+10.60	DOUBLE CENTERLINE, YELLOW	49
28+81.79 TO 41+17.33	DOUBLE CENTERLINE, YELLOW	2,471
TILSON STREET	DOUBLE CENTERLINE, YELLOW	72
IL RTE. 16		
44+12.96 TO 46+71.88	DOUBLE CENTERLINE, YELLOW	518
41+95.00 TO 44+57.00	DOUBLE CENTERLINE, YELLOW	524
IL RTE. 127		
00+54.80 TO 01+12.10	MEDIAN DOUBLE EDGE LINES, YELLOW	230
01+12.10 TO 03+59.24	MEDIAN EDGE LINES, YELLOW	494
01+12.10 TO 03+59.24	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	120
04+35.34 TO 05+30.68, LEFT	PARKING LANE LINE, WHITE	95
05+82.30 TO 06+25.16, LEFT	PARKING LANE LINE, WHITE	43
04+43.05 TO 07+61.70	MEDIAN EDGE LINES, YELLOW	638
04+43.05 TO 07+61.70	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	160
08+52.25 TO 12+77.88	MEDIAN EDGE LINES, YELLOW	852
08+52.25 TO 12+77.88	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	200
12+77.88 TO 14+33.73	MEDIAN DOUBLE EDGE LINES, YELLOW	625
14+33.73 TO 15+56.87	DOUBLE CENTERLINE, YELLOW	247
16+73.64 TO 17+98.76	DOUBLE CENTERLINE, YELLOW	251
17+98.76 TO 19+52.60	MEDIAN DOUBLE EDGE LINES, YELLOW	616
19+52.60 TO 20+26.40	MEDIAN EDGE LINES, YELLOW	148
19+52.60 TO 20+26.40	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	40
21+15.30 TO 21+94.90	MEDIAN EDGE LINES, YELLOW	159
21+15.30 TO 21+94.90	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	40
21+94.90 TO 23+22.85	MEDIAN DOUBLE EDGE LINES, YELLOW	512
23+22.85 TO 24+24.56	DOUBLE CENTERLINE, YELLOW	204
25+08.40 TO 26+09.50	DOUBLE CENTERLINE, YELLOW	203
26+09.50 TO 26+80.50	MEDIAN DOUBLE EDGE LINES, YELLOW	284
26+80.50 TO 33+00.00	MEDIAN EDGE LINES, YELLOW	1,239
26+80.50 TO 33+00.00	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	300
33+88.36 TO 35+92.23	MEDIAN EDGE LINES, YELLOW	408
33+88.36 TO 35+92.23	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	100
36+59.07 TO 39+00.00	MEDIAN EDGE LINES, YELLOW	482
36+59.07 TO 39+00.00	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	120
39+82.77 TO 43+92.23	MEDIAN EDGE LINES, YELLOW	819
39+82.77 TO 43+92.23	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	200
44+79.35 TO 49+53.00	MEDIAN EDGE LINES, YELLOW	948
44+79.35 TO 49+53.00	MEDIAN SKIP-DASH (30' -10') LINES, YELLOW	240
50+07.58 TO 53+87.00	LEFT PAVEMENT EDGE LINE, WHITE	385
50+36.41 TO 53+75.00	DOUBLE CENTERLINE, YELLOW	678
50+36.41 TO 58+08.91	RIGHT PAVEMENT EDGE LINE, WHITE	772
54+46.90 TO 58+08.91	MEDIAN DOUBLE EDGE LINES, YELLOW	1,448
54+80.45 TO 58+08.91	LEFT PAVEMENT EDGE LINE, WHITE	329

TOTAL = 18,263 FEET

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B, INLAID - LINE 5"		
LOCATION (STATION OR ROAD)	DESCRIPTION	QUANTITY (FOOT)
IL RTE. 16		
46+71.88 TO 50+00.00	CENTERLINE (30' SKIP - 10' DASH), YELLOW	90
STATION EQUATION: 50+00.00 BK. = 00+00.00 AHD.		
00+00.00 TO 9+84.08	CENTERLINE (30' SKIP - 10' DASH), YELLOW	250
BRIDGE OMISSION: 9+84.08 TO 10+83.69		
10+83.69 TO 44+57.00	CENTERLINE (30' SKIP - 10' DASH), YELLOW	780

GRAND TOTAL = 1,120 FEET

•-20RS-7, 21RS-6, 104RS, 105RS-4
••-325, 42

FILE NAME =
c:\pwork\pwi00\TLAUGHLIN\LAUGHLIN\05366\072C52-sht-schedule.dgn

USER NAME = laughlinr1
PLOT SCALE = 100.0000' / IN.
PLOT DATE = Mar-26-2010 11:59:22AM

DESIGNED - RTS	REVISED -
DRAWN - RTS	REVISED -
CHECKED - RTS	REVISED -
DATE - 3-10-10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 5 OF 8 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
••	•	MONTGOMERY	60	18
CONTRACT NO. 72C52			ILLINOIS FED. AID PROJECT	