

**SUMMARY OF QUANTITIES**

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE																			
				(25-3)B			(25-3)R				(25-3)BY			(25-3)BR									
				100% STATE ROADWAY J000-2A	100% STATE BRIDGE SN 025-0107 EB & SN 025-0108 X031-2A	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE ROADWAY J000-2A	100% STATE ROADWAY I000	100% STATE SIGNING Y002-1C	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE SN025-0099 SN025-0100 SETL-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2018 EB X228-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2017 WB X228-2A	100% STATE BRIDGE 025-0001 X271-2A	100% STATE BRIDGE 025-0018 X271-2A								
50300265	SEAL COAT CONCRETE	CU YD	710		710																		
50300280	CONCRETE ENCASEMENT	CU YD	70.8		70.8																		
50300300	PROTECTIVE COAT	SQ YD	7135.4		6091							26.4									819	199	
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	6387		6387																		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	17305																		7466	9839	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	26																		18	8	
50600600	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1																		1		
50600700	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1																			1	
50800105	REINFORCEMENT BARS	POUND	141,080						141,080														
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	790,760		681,600				1370				2050	43260	29800						12170	20510	
50800515	BAR SPLICERS	EACH	4015		3898																86	31	
51100100	SLOPE WALL 4 INCH	SQ YD	400																		48	352	
51201800	FURNISHING STEEL PILES HP 14X73	FOOT	17566	148	17344				74														
51202305	DRIVING PILES	FOOT	17566	148	17344				74														
51203800	TEST PILE STEEL HP14X73	EACH	12		12																		
51500100	NAME PLATES	EACH	4		2									1	1								
52000110	PREFORMED JOINT STRIP SEAL	FOOT	334		184																91	59	
52000320	NEOPRENE EXPANSION JOINT 2"	FOOT	232																		111	121	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	26																		18	8	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	28		28																		
52100505	ANCHOR BOLTS, 5/8"	EACH	56		56																		
52100520	ANCHOR BOLTS, 1"	EACH	36																		36		
52100530	ANCHOR BOLTS, 1 1/4"	EACH	166		32																72	62	
52100540	ANCHOR BOLTS, 1 1/2"	EACH	16																			16	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	248						118					96	34								
54003000	CONCRETE BOX CULVERTS	CU YD	891.5						463.7					255.3	172.5								
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	121						121														
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	204	14					190														
542A0253	PIPE CULVERTS, CLASS A, TYPE 1 48"	FOOT	9						9														
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	297	118					179														
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	27						27														
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	88						88														
542A1099	PIPE CULVERTS, CLASS A, TYPE 2 54"	FOOT	83						83														
542A1129	PIPE CULVERTS, CLASS A, TYPE 2 84"	FOOT	16						16														
542A1921	PIPE CULVERTS, CLASS A, TYPE 3 36"	FOOT	40						40														
542A2809	PIPE CULVERTS, CLASS A, TYPE 4 84"	FOOT	67						67														
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	36						36														
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	94						94														
542D0241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	39						39														
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	4						4														
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	2					2														
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2						2														
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	4						4														
54213729	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 84"	EACH	1						1														
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	2						2														

Rev. 7-14-10  
Rev. 5-26-10

FILE NAME = S:\Projects\1002727\1002727.dwg  
USER NAME = paul

DESIGNED - ESW  
DRAWN - ESW  
CHECKED - BRM  
DATE - 09-18-09

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**COMBINED SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	(25-3)R, BY, BR, B	EFFINGHAM	1416	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 74296	