

SUMMARY OF QUANTITIES

CODED NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				(25-3)B			(25-3)R			(25-3)Y			(25-3)BR		
				100% STATE ROADWAY J000-2A	100% STATE BRIDGE SN 025-0107 EB & SN 025-0108 X031-2A	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE ROADWAY J000-2A	100% STATE ROADWAY I000	100% STATE SIGNING Y002-1C	100% STATE IMPACT ATTENUATORS SFTY-3N	100% STATE SN025-0099 SN025-0100 SFTY-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2018 EB X228-2A	100% STATE BOX CULVERTS TUNNEL SN 025-2017 WB X228-2A	100% STATE BRIDGE 025-0001 X271-2A	100% STATE BRIDGE 025-0018 X271-2A
X0326571	TRAFFIC CONTROL SUPERVISOR	CAL DA	760				760								
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	862											388	474
X0325605	PAVEMENT MARKING GROOVING	SQ FT	401				401								
X0358300	REMOVE AND RELAY END SECTIONS	EACH	1				1								
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1										
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1										
X5020503	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 3	EACH	1		1										
X5020504	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 4	EACH	1		1										
X5041800	CONCRETE ANCHORS	EACH	30				30								
X5060601	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO.1	L SUM	1												
X5080600	MECHANICAL SPLICERS	EACH	1752		1548						204				
X5060602	CONTAINMENT AND DISPOSAL OF NON-LEAD PAINT CLEANING RESIDUES NO.2	L SUM	1												1
X6370250	CONCRETE BARRIER, VARIABLE CROSS SECTION 42" HEIGHT	FOOT	521				521								
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1				1								
X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	66911	11250			46147	9514							
X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	11031	1407			8795	829							
X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	6213				5589	624							
X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	1190				1103	87							
X2193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	591											591	
Z0012200	CONCRETE BRIDGE DECK SCARIFICATION (1/2 INCH)	SQ YD	652											652	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.2			0.76							0.02	0.02
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	25											14	11
Z0017100	DOWEL BARS	EACH	1204					1204							
Z0018800	DRAINAGE SYSTEM	L SUM	1												1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	9		1			7						1	
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1					1							
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	13		1			11						1	
Z0054505	ROCK FILL - REPLACEMENT	TON	791												
Z0065730	SLOPE WALL SLURRY PUMPING	CU YD	341												341
Z0076850	UNBOUND CONCRETE REMOVAL	SQ YD	15.8											10.8	5
A2C05005	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 5-GALLON	EACH	200				200								
A2C07003	TREE, TAXODIUM DISTICHUM (BALD CYPRESS), CONTAINER GROWN, 3-GALLON	EACH	200				200								
B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	350				350								
B2001464	TREE, CORNUS MAS (CORNELIAN CHERRY DOG WOOD), 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	200				200								
B2006316	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	200				200								
C2002048	SHRUB, CORYLIUS AMERICANA (AMERICAN FILBERT), 4' HEIGHT, BALLED AND BURLAPPED	EACH	875				875								
C2005905	SHRUB, RHUS GLABRA (SMOOTH SUMAC), 5-GALLON	EACH	875				875								
C2C00363	SHRUB, AMOUPIA FRUITCOSA (INDIGO BUSH), CONTAINER GROWN, 3-GALLON	EACH	875				875								
C2C00663	SHRUB, ARONIA MELANOCARPA VIKING (VIKING BLACK CHOKEBERRY), CONTAINER GROWN, 3-GALLON	EACH	875				875								
C2C005724	SHRUB, RHUS AROMATICA (FRAGRANT SUMAC), 2' WIDTH, CONTAINER	EACH	875				875								
C2C11624	SHRUB, VIBURNUM CARLESI (KOREANSPICE VIBURNUM), 2' HEIGHT, CONTAINER	EACH	875				875								
C2C11736	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 3' HEIGHT, CONTAINER	EACH	860				860								
D2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	210				210								
X7800100	PREFORMED THERMOPLASTIC PAVEMENT MARKING SHIELD	EACH	4				4								
Z0076502	TRAFFIC MANAGEMENT SYSTEM	CAL MD	25												
X0023800	REMOVE AND RELOCATE INLETS	EACH	1	1											
Z0076504	TRAFFIC MANAGEMENT SYSTEM INSTALLATION	L SUM	1												
X0326845	SERVICE PROVIDER	CAL MD	25				25								
X7011008	TRAFFIC CONTROL AND PROTECTION FOR ALTERNATE ROUTE SIGNING	CAL MD	25				25								
X7011012	TRAFFIC CONTROL AND PROTECTION FOR ALTERNATE ROUTE	L SUM	1												
X7017026	TRAFFIC CONTROL AND PROTECTION, CASE I	EACH	12				12								
X7017027	TRAFFIC CONTROL AND PROTECTION, CASE II	EACH	8				8								
X7017028	TRAFFIC CONTROL AND PROTECTION, CASE III	EACH	12				12								

* Specialty Items

Rev. 7-14-10
Rev. 5-26-10