



ROADWAY C						
POINT	ELEVATION	NORTHING	EASTING	ROADWAY STATION	± ROADWAY OFFSET	RAMP STATION
ROADWAY A						
100	577.77	886,376.49	915,391.05	2069+95.07	12.00	10+00.00
101	577.58	886,359.02	915,381.09	2069+75.00	12.27	10+20.10
102	577.35	886,337.27	915,368.67	2069+50.00	12.68	10+45.15
103	577.12	886,315.56	915,356.17	2069+25.00	13.09	10+70.20
104	576.89	886,293.90	915,343.59	2069+00.00	13.50	10+95.26
105	576.66	886,272.28	915,330.92	2068+75.00	13.89	11+20.31
106	576.43	886,250.72	915,318.16	2068+50.00	14.23	11+45.37
107	576.20	886,229.20	915,305.32	2068+25.00	14.68	11+70.42
108	575.97	886,207.74	915,292.40	2068+00.00	15.06	11+95.48
109	575.74	886,186.32	915,279.39	2067+75.00	15.43	12+20.54
110	575.51	886,164.95	915,266.29	2067+50.00	15.80	12+45.60
111	575.28	886,143.64	915,253.12	2067+25.00	16.16	12+70.66
112	575.05	886,122.37	915,239.85	2067+00.00	16.52	12+95.72
113	574.82	886,101.16	915,226.50	2066+75.00	16.87	13+20.79
114	574.59	886,079.99	915,213.07	2066+50.00	17.21	13+45.85
115	574.35	886,058.88	915,199.56	2066+25.00	17.55	13+70.92
116	574.12	886,037.82	915,185.96	2066+00.00	17.88	13+95.98
117	573.89	886,016.82	915,172.28	2065+75.00	18.21	14+21.05
118	573.66	885,995.86	915,158.52	2065+50.00	18.53	14+46.12
119	573.43	885,974.96	915,144.67	2065+25.00	18.84	14+71.19
120	573.19	885,954.12	915,130.74	2065+00.00	19.15	14+96.27
121	572.96	885,933.33	915,116.73	2064+75.00	19.45	15+21.34
122	572.73	885,912.59	915,102.63	2064+50.00	19.74	15+46.41

FILE NAME =	USER NAME = paul	DESIGNED - ESW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT ELEVATION DETAIL, ROADWAY C, SOUTH TRI LEVEL			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
5:\projects\400-88872-57-70\400-88872-57-70.dgn		DRAWN - PDB	REVISED -					57/70	(25-3)R	EFFINGHAM	1416	322	
		CHECKED - BRM	REVISED -		SCALE: 1"=20'			SHEET NO. 4 OF 12 SHEETS	STA. 2070+32.80(A) TO STA. 2064+50.00(A)	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 74296	
		DATE - 2-29-08	REVISED -										