

**PAVING SCHEDULE**

LOCATION	SIDE	PORTLAND CEMENT CONCRETE PAVEMENT 12" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	AGGREGATE (PRIME COAT) (TON)	TEMPORARY RAMP (SQ YD)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105 (TON)	MATERIAL TRANSFER DEVICE (TON)	PAVEMENT FABRIC (SQ YD)	HOT-MIX ASPHALT SHOULDERS (TON)
STATION TO STATION									
LOCATION 1: SN 025-0001									
5024+94.60 TO 5028+26.40	LT	352						352	
5027+51.40 TO 5028+52.65	RT	48						48	
5027+86.06 TO 5028+56.06	LT/RT		21	0.4	26	21	21		6.2
5030+40.73 TO 5031+10.73	LT/RT		19	0.4	23	20	20		4.6
5030+43.00 TO 5034+66.50	LT	381						381	
5030+84.40 TO 5034+95.91	RT	194						194	
LOCATION 1 SUBTOTAL		975	40	1	49	41	41	975	11
	TOTAL	975	40	1	49	41	41	975	11

**REMOVAL SCHEDULE**

LOCATION	SIDE	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT (SQ YD)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT (SQ YD)	PAVED SHOULDER REMOVAL (SQ YD)
STATION TO STATION				
LOCATION 1: SN 025-0001				
5024+94.60 TO 5028+26.40	LT			349
5027+51.40 TO 5028+52.90	RT			38
5027+86.06 TO 5028+56.06	LT/RT	208	64	
5030+40.73 TO 5031+10.73	LT/RT	204	47	
5030+43.00 TO 5034+66.50	LT			373
5030+84.40 TO 5034+95.90	RT			190
LOCATION 1 SUBTOTAL		412	111	950
	TOTAL	412	111	950

**TRAFFIC CONTROL SCHEDULE**

LOCATION	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
STATION TO STATION				
LOCATION 1: SN 025-0001				
5028+49.50 TO 5032+37.02	400	400	1	1
LOCATION 1 SUBTOTAL	400	400	1	1
	TOTAL	400	1	1

**PAVEMENT MARKING SCHEDULE**

LOCATION	SHORT-TERM PAVEMENT MARKING		TEMPORARY PAVEMENT MARKING - LINE 4"		TEMPORARY PAVEMENT MARKING - LINE 6"	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
	YELLOW (FOOT)	WHITE (FOOT)	SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)	SKIP DASH WHITE (FOOT)	
STATION TO STATION						
LOCATION 1: SN 025-0001						
5026+18.06 TO 5028+56.06						
5027+86.05 TO 5028+56.06	4	8	81.3	60.6	17.5	56.0
5028+56.06 TO 5030+40.60						
5030+40.60 TO 5031+10.73	4	8	82.2	57.8	17.5	55.4
5030+40.60 TO 5035+00.00						
LOCATION 1 SUBTOTAL	8	16	163.5	118.4	35	111.4
	TOTAL	24		282	35	112

FILE NAME =  
S:\Projects\081002157-7\4p10-Report\South\shchd1.mxd

USER NAME = paul  
PLOT SCALE = 100.0000' / IN.  
PLOT DATE = 3/17/2010

DESIGNED - ESW  
DRAWN - PDB  
CHECKED - BRM  
DATE - 07-21-08

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	(25-3)BR	EFFINGHAM	1416	1343
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74296	