

SUMMARY OF QUANTITIES

F&P ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
310	60-16-181B,42-181B	MADISON AND JERSEY	481	9
STA		TO STA		
EXISTING CONDITIONS:				
CONTRACT NO. 76318				

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				
				JERSEY COUNTY				MADISON COUNTY
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE (ARCH)	80% FEDERAL 20% STATE BRIDGE (BEAM)	80% FEDERAL 20% STATE RETAINING WALL	80% FEDERAL 20% STATE ROADWAY
CODE NUMBER	ITEM	UNITS	TOTAL	I000-2A	X024-2A	X081-2A	Y007	I000-2A
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	478	478				
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	140					140
54244805	INLET BOX, STANDARD 542501	EACH	3	2				1
54245005	INLET BOX, STANDARD 542521	EACH	1	1				
54245205	INLET BOX, STANDARD 542511	EACH	5	5				
54246205	INLET BOX TYPE 542526	EACH	2	2				
54248510	CONCRETE COLLAR	CU YD	24.8	24.8				
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	529	485				44
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	1,085	1,085				
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	78	78				
542A1909	PIPE CULVERTS, CLASS A, TYPE 3 24"	FOOT	235	194				41
542A2797	PIPE CULVERTS, CLASS A, TYPE 4 72"	FOOT	207	207				
542A3379	PIPE CULVERTS, CLASS A, TYPE 5 24"	FOOT	75	75				
542A4009	PIPE CULVERTS, CLASS A, TYPE 6 24"	FOOT	305	259				46
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	432	432				
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	164	164				