FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
310	60-16-1&1B,42-1&1B	MADISON AND JERSEY	481	38
STA.		TO STA.		
EXISTING CONDITIONS:				

CULVERTS - SIDE ROADS

CONTRACT NO. 76318

STATION	STATION	OFFSET	PIPE CULVERTS (FT) CLASS A TYPE 1 24"	CLASS A TYPE 1 24" (TEMPORARY)	CLASS A TYPE 2 24"	CLASS A TYPE 2 48"	CLASS A TYPE 3 24"	CLASS A TYPE 4 72"	CLASS A TYPE 5 24"	CLASS A TYPE 6 24"	CLASS A JACKED 24"	CLASS A JACKED 72"	CLASS D TYPE 1 15"	CLASS D TYPE 1 18"	CLASS D TYPE 1 24"	CLASS D TYPE 2 15"	CLASS D TYPE 2 18"	CLASS D TYPE 2 24"	CLASS D TYPE 2 72"	CLASS D TYPE 1 12" (TEMPORARY)	BOX CULV END SEC (EACH)	END SECTIONS 15" (EACH)	END SECTIONS 18" (EACH)	METAL END SECTION 24" (EACH)	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 72"	PRECAST CONC BOX CULVERT (FOOT) 3' X2'	CONCRETE BOX CULVERT (CU YD)	REINFORCEMENT BARS (LBS)	PRECAST REINFORCED CONCRETE FLARED END SECTION (EACH) 12"	PRECAST REINFORCED CONCRETE FLARED END SECTION (EACH) 24"	PRECAST REINFORCED CONCRETE FLARED END SECTION (EACH) 48"	RC PIPE TEE 24" PIPE W/ 24" RISER (EACH)	CONCRETE COLLARS (CU YD)	INLET BOX STD 542501 (EACH)	INLET BOX STD 542511 (EACH)	INLET BOX TYPE 24F (EACH)	MAN TA 5' DIA TIF CL (EACH)	MAN TA 5D M IN STD 604101 (EACH)	MAN TA 6D M IN STD 604101 (EACH)	INLET TY A W/TYPE 8 F&G (24" DEPTH) (EACH)	MEDIAN INLET STD 604101 (EACH)	REMARKS
329+00		CL																		24																								
329+00		RT																		36																								
331+32		LT/MED													88					24																								
331+32		RT																		36																								
333+46		LT			59																										1					1							
335+00		LT/MED																46		24																								
SUBTOTAL MAINLINE			326	140	851	0	213	207	75	305	246	144	78	0	143	117	0	46	0	408	6	0	0	2	3	2	172	225.5	57920	1	12	0	1	24.8	3	5	2	6	3	0	0	2	0
QUARRY ROAD																																												
55+79		LT																				1																						
56+00		LT											46																															
56+16		LT																				1																						
57+72		AR			42																										1								1					
57+72		RT					22																								1													
63+00		AR				78																										1								1				
65+00		AR															62						2																					
JUN ACCESS																																												
21+46		AR											52																													1		
23+50		AR											32																															
CONNECTOR ROAD																																												
50+89		AR	58																												2													
52+71		AR	54																												2													
DOMINO LANE SERVICE ROAD																																												
102+00		AR													48																													
103+42		RT												29																														
105+29		RT												27																														
106+60		RT												26																														
110+45		RT												18																														
111+73		RT												32																														
DOMINO LANE																																												
10+30		AR												32																														
NORTH INGHAM																																												
145+70		AR													34																													
148+60		LT																							1																			
148+85		AR			135																																							
149+09		RT																							1																			
151+15		AR	91																																									
151+40		RT																							1																			
152+75		LT											44																															
154+90		AR			57																										2													
INGHAM ACCESS DRIVE																																												
174+88		AR																	108																									
INGHAM RUNAROUND																																												
201+05		AR																		50																								
STAGECOACH ROAD																																												
194+66		AR													50																													
196+00		LT											36																															
202+48		RT											36																															
203+48		LT											38																															
204+37		RT											34																															
204+76		RT											36																															
TRINITY RUNAROUND																																												
210+55		AR																		20																								
SUBTOTAL SIDEROADS			203	0	234	78	22	0	0	0	0	0	354	164	132	0	62	0	108	70	0	2	2	0	3	0	0	0	0	0	8	1	0	0	0	0	0	0	1	1	1	0	
SUBTOTAL MAINLINE			326	140	851	0	213	207	75	305	246	144	78	0	143	117	0	46	0	408	6	0	0	2	3	2	172	225.5	57,920	1	12	0	1	24.8	3	5	2	6	3	0	0	2	
PROJECT TOTAL			529	140	1,085	78	235	207	75	305	246	144	432	164	275	117	62	46	108	478	6	2	2	2	6	2	172	225.5	57,920	1	20	1	1	24.8	3	5	2	6	4	1	1	2	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 310
SECTION 60-16-1&1B,42-1&1B
MADISON AND JERSEY COUNTIES

DRAWN BY: RLK CHECKED BY: CAS

$$DATE$$
•DATE-TIME•
•DGN-SPEC•
•REF•
•REF•