



* Fabricator shall locate to miss strands within permissible tolerances.

$\frac{3}{4}$ " ϕ A307 Bolts with lock nuts, typ. Bolts through the concrete web shall be tightened to snug tight only.

		0.4 Sp. #1 or 0.6 Sp. #3	Pier 1 or 2	0.5 Span 2
I	(in ⁴)	144117		144117
I'	(in ⁴)	398900		398900
S _b	(in ³)	6834		6834
S _b '	(in ³)	11230		11230
S _t	(in ³)	5355		5355
S _t '	(in ³)	32000		32000
M _Q	(k/')	1.296		1.296
M _L	(k)	720		1313
s _Q	(k/')	.506	.506	.506
M _{sQ}	(k)	141	322	191
M _L	(k)	506	474	556
M (Imp)	(k)	132	117	129


		Abuts.	Pier 1 Span 1 Pier 2 Span 3	Pier 1 Span 2 Pier 2 Span 2
R _Q	(k)	44	44	58
R _{sQ}	(k)	12	22	22
R _L	(k)	40	29	29
Imp.	(k)	10	7	7
R (Total)	(k)	106	102	116

I and I' are the moment of inertia and composite moment of inertia of the beam section.
 S_b and S_b' are the non-composite and composite section modulus for the bottom fiber of the prestressed beam.
 S_t and S_t' are the non-composite and composite section modulus for the top fiber of the prestressed beam.
 M_Q is the moment due to dead loads on the non-composite prestressed beam. It is conservatively calculated at 0.5 of the span.
 M_{sQ} is the moment due to dead loads on the composite section.
 M_L is the moment due to live load on the composite section.
 M (Imp) is the moment due to live load impact on the composite section.
 R (Total) is the sum of the reaction per bearing due to R_Q (non-composite) + R_{sQ} (composite) + R_L + I (composite).



Notes:
 All material for bracing shall be hot dip galvanized according to AASHTO M111 unless otherwise noted. Two hardened washers are required for each set of oversized holes.
 All holes shall be $\frac{5}{16}$ " ϕ unless otherwise noted. $\frac{5}{16}$ " x 3" x 3" plate washers are required over all slotted holes.
 All bolts shall be galvanized according to AASHTO M232. Bracing shall be installed as beams are erected and tightened as soon as possible during erection.
 Permanent bracing shall not be paid for separately, but shall be included in the cost of Furnishing and Erecting Precast Prestressed Concrete I-Beams.

**PERMANENT BRACING DETAILS FOR
 48" PPC I-BEAM**



DESIGNED	R.K.M.
CHECKED	M.E.B.
DRAWN	P.W.S.
CHECKED	M.E.B.-R.K.M.

FRAMING PLAN

**FRAMING PLAN
 SOUTHBOUND LANES
 FAP-310
 SECTION 60-16-1, 42-1
 JERSEY COUNTY
 STATION 318+48.66
 STRUCTURE NO. 042-0026 (S.B.)**

HR
 HURST-ROSCHE
 ENGINEERS, INC.
 601 NORTH BRUNS LANE
 SPRINGFIELD, IL 62702
 (217)-787-1199
 FAX (217)-793-1199