CONTRACT NO. 76A47

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	(133,134)RS-5,135RS-6	ST. CLAIR	762	62
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SIGN SCHEDULE

LOCATION	EXISTING STATION	EXISTING OFFSET	EXISTING SIGN	EXISTING SIZE	EXISTING POST	EXISTING DESCRIPTION	REMOVE SIGN PANEL TYPE 1 SQ FT	REMOVE SIGN PANEL TYPE 2 SQ FT	REMOVE SIGN PANEL TYPE 3 SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE A SQ FT	REMOVE SIGN PANEL ASSEMBLY TYPE B SQ FT	REMOVE GROUND MOUNTED SIGN SUPPORT EACH	PROPOSED STATION	PROPOSED OFFSET	PROPOSED SIGN	PROPOSED SIZE	PROPOSED SIGN PANEL TYPE 1 SQ FT	PROPOSED SIGN PANEL TYPE 2 SQ FT	PROPOSED RELOCATE SIGN PANEL ASSEMBLY TYPE A SQ FT	PROPOSED RELOCATE SIGN PANEL ASSEMBLY TYPE B SQ FT	PROPOSED WOOD SIGN SUPPORT FT	ACTION
268	530+96.33	-50.41	N/A	8' X 4'	2 WOOD POST'S	THE HENRY WHITE EXPERIMENTAL FARM																REMAIN IN PLACE
			N/A	7' X 16"		FIELD DAY																REMAIN IN PLACE
			N/A	8' X 4'		THE HENRY WHITE EXPERIMENTAL FARM																REMAIN IN PLACE
			N/A	7' X 16"		FIELD DAY																REMAIN IN PLACE
269	524+12.88	-45.97	N/A	48 X 45	2 WOOD POST'S	THE HENRY WHITE EXPERIMENTAL FARM NEXT LEFT																REMAIN IN PLACE
269A	516+78.35	-44.45	N/A	14 X 10	METAL POST	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
270	511+07.00	-34.00	N/A	8' X 42"	2 WOOD POST'S	WELCOME TO MILLSTADT SIGN					36	2										REMOVE
			N/A	48 X 24		SISTER CITY CROSS-BIEBERAU HESSEN GERMANY																REMOVE
271	496+35.25	-35.10	R1-1	30 X 30	METAL POST	STOP SIGN	6.3					1			R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
272	496+27.64	-33.77	D3-1	24 X 6	METAL POST	STREET SIGN "KRISTA LN"	1					1										REMOVE
273	496+27.64	-32.77	N/A	6 X 18	METAL POST	HYD																REMOVE
273A	496+28.59	-51.33	N/A	14 X 10	METAL PIPE	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
273B	495+94.20	-49.32	N/A	14 X 10	METAL POST	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
273C	495+88.61	-101.14	N/A	14 X 10	GAS VALVE PROTECTION BOLLARD	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
274	492+44.02	-26.00	S3-1	36 X 36	WOOD POST	SCHOOL BUS STOP AHEAD	9					1										REMOVE
274A	482+48.52	-55.16	N/A	14 X 10	METAL POST	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
275	475+03.74	-21.20	W2-2	30 X 30	WOOD POST	INTERSECTION SIDE ROAD RIGHT					19	1	475+04	35' LT	W2-2	30 X 30	6.3				18	NEW SIGN PANEL AND WOOD POST
			W16-8	30 X 12		SPRING LAKE ROAD									W16-8	30 X 12	2.5					NEW SIGN PANEL AND WOOD POST
			W14-3	48 X 60 X 60		NO PASSING ZONE									W14-3	48 X 60 X 60		10				NEW SIGN PANEL AND WOOD POST
276	469+32.15	-32.98	R1-1	30 X 30	TEL. STEEL WO/SLEEVE	STOP SIGN	6.3					1	469+32		R1-1	30 X 30						NEW SIGN PANEL AND WOOD POST
277	469+28.78	-66.23	N/A	7' X 2'	BRICK FOUNDATION	BUFFWOOD																REMAIN IN PLACE
277A	469+07.42	-48.67	N/A	14 X 10	METAL PIPE	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
278	466+17.38	-31.48	W1-4R	30 X 30	WOOD POST	ROAD CURVES RIGHT THEN LEFT AHEAD	6.3					1	466+17	35' LT	W1-4R	30 X 30	6.3				14	NEW SIGN PANEL AND WOOD POST
279	465+67.88	-33.46	D3-1	28 X 6	TEL. STEEL W/SLEEVE	STREET SIGN "DAVIDSON DR"				2.4		1										REMOVE
			D3-1	28 X 6		STREET SIGN "DAVIDSON DR"																REMOVE
279A	458+68.85	-27.50	N/A	14 X 10	METAL PIPE	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
280	450+89.77	-19.40	R2-5	30 X 36	WOOD POST	SPEED ZONE AHEAD					9.8		450+90	40' LT	R2-5	30 X 36	7.5				17	NEW SIGN PANEL AND WOOD POST
			R2-1101	18 X 18		35 M.P.H.									R2-1101	18 X 18	2.3					NEW SIGN PANEL AND WOOD POST
281	446+02.38	-40.16	N/A	36 X 24	2 WOOD POST'S	ST. CLAIR COUNTY ANGLERS MEMBERS ONLY	6					2										REMOVE
282	445+60.76	-30.56	R1-1	30 X 30	TEL. STEEL WO/SLEEVE	STOP SIGN	6.3					1	446+02		R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
283	440+79.23	-21.25	R2-1	24 X 30	TEL. STEEL WO/SLEEVE	SPEED LIMIT 35	5					1	440+79	35' LT	R2-1	24 X 30	5				15.5	NEW SIGN PANEL AND WOOD POST
284	440+54.47	-66.48	N/A	8' X 8'-4"	STEEL SUPPORT	1ST NATIONAL BANK OF WATERLOO BILLBOARD																REMAIN IN PLACE
285	439+95.38	-20.73	W2-2	30 X 30	TEL. STEEL WO/SLEEVE	INTERSECTION SIDE ROAD RIGHT	6.3					1	439+95	35' LT	W2-2	30 X 30	6.3				16.5	NEW SIGN PANEL AND WOOD POST
285A	438+25.37	-38.20	N/A	14 X 10	METAL POST	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
286	437+08.07	-60.07	N/A	8' X 12'	2 STEEL SUPPORT'S	MILLSTADT IGA BILLBOARD																REMAIN IN PLACE
287	437+09.32	-30.98	R1-1	30 X 30	TEL. STEEL W/SLEEVE	STOP SIGN	6.3					1			R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
288	435+33.19	-45.15	D3-1	30 X 6	METAL POST	STREET SIGN "WHEATRIDGE"				2.8		1										REMOVE
			D3-1	36 X 6		STREET SIGN "E. WASHINGTON ST"																REMOVE
289	434+92.15	-33.92	R1-1	30 X 30	TEL. STEEL WO/SLEEVE	STOP SIGN	6.3					1	437+09		R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
290	433+87.24	-21.26	R2-1	24 X 30	WOOD POST	SPEED LIMIT 35				14.2		1	433+87	21.5' LT	R2-1	24 X 30	5				16	NEW SIGN PANEL AND WOOD POST
			W14-3	48 X 60 X 60		NO PASSING ZONE									W14-3	48 X 60 X 60		10				NEW SIGN PANEL AND WOOD POST
291	431+85.18	-52.39	N/A	8' X 3'	3 WOOD POST'S	TRINITY LUTHERAN CHURCH																REMAIN IN PLACE
291A	430+03.86	-34.66	N/A	14 X 10	METAL POST	WARNING BURIED GAS PIPELINE																REMAIN IN PLACE
292	428+82.61	-38.47	N/A	8' X 4'	2 STEEL SUPPORT'S	TRINITY LUTHERAN CHURCH CHANGEABLE MESSAGE SIGN																REMAIN IN PLACE
293	428+43.75	-26.95	R2-1	24 X 30	TEL. STEEL WO/SLEEVE	SPEED LIMIT 30	5					1	428+44	21.5' LT	R2-1	24 X 30	5				14.5	NEW SIGN PANEL AND WOOD POST
294	427+59.17	-24.63	OM-3R	12 X 36	METAL POST	OBJECT MARKER RIGHT	3															REMOVE
295	427+12.59	-27.80	R1-1	30 X 30	METAL POST	STOP SIGN	6.3					1			R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
296	427+07.00	-30.92	D3-1	30 X 6	METAL POST	STREET SIGN "N. BALTZ ST"				3		1										REMOVE
			D3-1	42 X 6		STREET SIGN "E. WASHINGTON AVE"																REMOVE
297	422+04.86	-44.24	N/A	10' X 10'	2 STEEL SUPPORT'S	CASEYS GENERAL STORE BILLBOARD																REMAIN IN PLACE
298	420+49.54	-27.36	R1-1	30 X 30	METAL POST	STOP SIGN	6.3					1			R1-1	30 X 30	6.3					NEW SIGN PANEL AND WOOD POST
299	420+49.21	-24.17	D3-1	36 X 6	METAL POST	STREET SIGN "N. KOSHUTH ST"				3.3		1										REMOVE
			D3-1	42 X 6		STREET SIGN "E. WASHINGTON AVE"																REMOVE
300	419+88.94	-32.50	N/A	8' X 8'	STEEL SUPPORT	SCHMIDT CHIROPRACTIC																REMAIN IN PLACE
301	418+69.90	-19.44	R2-1	24 X 30	WOOD POST	SPEED LIMIT 30					10.6	1	418+70	26' LT	R2-1	24 X 30	5				15	NEW SIGN PANEL AND WOOD POST
			W14-3	36 X 48 X 48		NO PASSING ZONE									W14-3	36 X 48 X 48	6					NEW SIGN PANEL AND WOOD POST
302	417+02.93	-32.64	R1-1	30 X 30	METAL POST	STOP SIGN																REMAIN IN PLACE
303	417+00.53	-29.81	D3-1	36 X 6	METAL POST	STREET SIGN "N. MULBERRY ST"																REMAIN IN PLACE
			D3-1	42 X 6		STREET SIGN "E. WASHINGTON AVE"																REMAIN IN PLACE
304	416+90.50	-28.76	N/A	24 X 9	WOOD POST	BARBER SHOP																REMAIN IN PLACE
			N/A	24 X 9		HAIRCUTS $8.00																REMAIN IN PLACE
305	414+00.04	-31.24	N/A	8' X 3'	STEEL SUPPORT	AC DELCO MUSKOPF GARAGE INC																REMAIN IN PLACE
			N/A	6' X 3'		CHANGEABLE MESSAGE SIGN																REMAIN IN PLACE
306	413+95.52	-20.13	N/A	12 X 18	POWER POLE	GOLDEN DIPT DELIVERIES AHEAD																REMAIN IN PLACE
307	413+48.50	-38.07	R1-1	30 X 30	METAL POST	STOP SIGN																REMAIN IN PLACE
308	413+48.51	-29.00	D3-1	30 X 6	METAL POST	STREET SIGN "N. BREESE ST"																REMAIN IN PLACE
			D3-1	42 X 6		STREET SIGN "E.WASHINGTON AVE"																REMAIN IN PLACE
309	412+97.23	-20.15	M2-1	21 X 15	WOOD POST	JUNCTION AUXILIARY SIGN																REMAIN IN PLACE
			M1-1100	30 X 24		ILLINOIS 163																REMAIN IN PLACE
310	412+86.19	-27.49	N/A	36 X 48	2 WOOD POST'S	FIRST NATIONAL BANK 24 HOUR ATM																REMAIN IN PLACE
311	411+16.79	-19.37	N/A	12 X 18	POWER POLE	GOLDEN DIPT DELIVERIES LEFT																REMAIN IN PLACE

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 809
SECTION (133,134)RS-5, 135RS-6
ST. CLAIR COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 9/15/2009
FILE NAME = c:\pw_work\PWIDOT\KARLASAL\dms51289\sch801902a.dgn
PLOT SCALE = 52.5412 ' / IN.
REFERENCE = REF