

SUMMARY OF QUANTITIES

				ST. CLAIR COUNTY																
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	RET. WALL	CULVERT	CONSTRUCTION TYPE CODE												
				I-70 20% STATE 80% FED	I-70 20% STATE 80% FED	I-70 20% STATE 80% FED	I-70 20% STATE 80% FED													
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	1,162	1,162																
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	339	339																
50102400	CONCRETE REMOVAL	CU YD	5.2				5.2													
50200100	STRUCTURE EXCAVATION	CU YD	462		462															
50300225	CONCRETE STRUCTURES	CU YD	1,456.1		1,452.3		3.8													
50300255	CONCRETE SUPERSTRUCTURE	CU YD	4,076.2		4,076.2															
50300260	BRIDGE DECK GROOVING	SQ YD	11,530		11,530															
50300300	PROTECTIVE COAT	SQ YD	14,509		14,509															
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1															
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1,150		1,150															
50500505	STUD SHEAR CONNECTORS	EACH	31,625		31,625															
50800105	REINFORCEMENT BARS	POUND	680,740		680,740															
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,476,680		1,475,060		1,620													
50800515	BAR SPLICERS	EACH	97		97															
51500100	NAME PLATES	EACH	2		2															
51602000	PERMANENT CASING	FOOT	2,447		2,447															
* 51603000	DRILLED SHAFT IN SOIL	CU YD	2,579		2,579															
* 51604000	DRILLED SHAFT IN ROCK	CU YD	57		57															
52100520	ANCHOR BOLTS, 1"	EACH	88		88															
52100530	ANCHOR BOLTS, 1 1/4"	EACH	264		264															
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2																
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1																
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1																
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1																
54215559	METAL END SECTIONS 24"	EACH	8	8																
54215565	METAL END SECTIONS 30"	EACH	2	2																
5422A030	PIPE CULVERTS, CLASS A, TYPE 2 30" (TEMPORARY)	FOOT	70	70																
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	66	66																
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	123	123																
542D1057	PIPE CULVERTS, CLASS D, TYPE 2 12"	FOOT	19	19																

* DENOTES SPECIALTY ITEMS

\\BDC\BDC\05-LEGENO.DGN, \\BDC\BDC\05-MOTIF.DGN, \\BDC\BDC\05-LEGENO.DGN, \\BDC\BDC\05-MOTIF.DGN
 6-03-2010 14:32:40 BID\HJLD \FS-8844\ANVAULT.DTRANS.87\2202\2008-08\1\CIVIL\CAD\99 ALL CONTRACTS\CONNSHEETS CONTRACT 05\BDC\05-SHT-SUMMARY2.DGN

FILE NAME = #FILEL#	USER NAME = #USER#	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION I-70 CONNECTION					SUMMARY OF QUANTITIES 2			F.A.P. RTE. 998	SECTION 82-2-1HVB	COUNTY ST. CLAIR	TOTAL SHEETS 285	SHEET NO. 5	
		DRAWN - JB	REVISED -									SCALE: N.T.S.		SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT	
		CHECKED - ACL	REVISED -													CONTRACT NO. 76C44	
		DATE - 06/04/10	REVISED -														

