SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY (80% FED. 20% STATE URBAN)	ST. CLAIR COUNTY ROADWAY I-70	BRIDGE I-70	RET. WALL I-70	CULVERT I-70								
				CONSTRUCTION TYPE CODE											
				J000-2A	X571-2A	Y007	Y007								
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	23	23											
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	90	90											
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	38	38											
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	78	78											
550B0450	STORM SEWERS, CLASS B, TYPE 2 36"	FOOT	89	89											
550B0770	STORM SEWERS, CLASS B, TYPE 3 42"	FOOT	1,621	1,621											
55100200	STORM SEWER REMOVAL 6"	FOOT	554	554											
55100300	STORM SEWER REMOVAL 8"	FOOT	214	214											
55100400	STORM SEWER REMOVAL 10"	FOOT	75	75											
55100900	STORM SEWER REMOVAL 18"	FOOT	48	48											
55101200	STORM SEWER REMOVAL 24"	FOOT	694	694											
55101600	STORM SEWER REMOVAL 36"	FOOT	35	35											
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	4	4											
58700300	CONCRETE SEALER	SQ FT	1,73		1,73										
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	10	10											
60107700	PIPE UNDERDRAINS 6"	FOOT	150	150											
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2											
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3											
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1											
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10	10											
60228120	MANHOLES, SANITARY, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8	8											
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1											
60240300	INLETS, TYPE B, TYPE 7 GRATE	EACH	1	1											
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1	1											
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1											
60500040	REMOVING MANHOLES	EACH	5	5											
* 63000135	STEEL PLATE BEAM GUARD RAIL, TYPE B (SPECIAL)	FOOT	475	475											
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1											
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	62.5	62.5											
66400305	CHAIN LINK FENCE, 6'	FOOT	6,943	6,943											

• DENOTES SPECIALTY ITEMS

\\DBCONN-05-BDRDSRL.DGN \\DBCONN-05-SDDL.DGN \\DBCONN-99-MOTIF.LDGN \\DBCONN-05-LEGEND.LDGN \\DBCONN-05-MOTIF.LDGN
6-03-2010, 14:32:57 BONDHULD \\FS-2014\AM\VAULT\J-TRANS\07\2282\28868-001\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 05\DBCONN-05-SHT-SUMMARY3.DGN

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -
		DRAWN - JB	REVISED -
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -
	PLOT DATE = $DATE$	DATE - 06/04/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
I-70 CONNECTION

SUMMARY OF QUANTITIES 3

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-2-1HVB	ST. CLAIR	285	6
		CONTRACT NO. 76C44		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		