

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ST. CLAIR COUNTY												
				80% FED. 20% STATE URBAN	ROADWAY I-70	BRIDGE I-70	RET. WALL I-70	CULVERT I-70	CONSTRUCTION TYPE CODE							
				J000-2A	X571-2A	Y007	Y007									
66407800	CHAIN LINK GATES, 6' X 16' DOUBLE	EACH	1	1												
66408200	CHAIN LINK GATES, 6' X 24' DOUBLE	EACH	4	4												
66410300	CHAIN LINK FENCE REMOVAL	FOOT	302	302												
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	14	14												
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	101,371	101,371												
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1												
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	10	10												
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24												
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	24	24												
67100100	MOBILIZATION	L SUM	1	1												
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1												
* 72000100	SIGN PANEL - TYPE 1	SQ FT	18	18												
* 73000100	WOOD SIGN SUPPORT	FOOT	48	48												
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7												
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	64	64												
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1												
X0321598	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1												
X0321720	WATER MAIN REMOVAL	FOOT	2,592	2,592												
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	20	20												
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	8,337	8,337												
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	4	4												
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3	3												
X0324774	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,088	1,088												
X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	1,088	1,088												
X0325627	HIGH LOAD MULTI-ROTATION BEARINGS, FIXED - 900K	EACH	33	33												
X0325628	HIGH LOAD MULTI-ROTATION BEARINGS, FIXED - 1000K	EACH	11	11												
X0325642	HIGH LOAD MULTI-ROTATION BEARINGS, GUIDED EXPANSION, 300K	EACH	22	22												
X0325833	WICK DRAINS	FOOT	119,845	119,845												
X0326802	UTILITY STRUCTURE REMOVAL	EACH	15	15												
X2010505	CLEARING, SPECIAL	L SUM	1	1												

• DENOTES SPECIALTY ITEMS

FILE NAME = ... \FS-8044\... \CONTRACTS\CONNSHEETS CONTRACT 85\08CONN-85-SHT-SUMMARY4.DGN  
DESIGNED - JB  
DRAWN - JB  
CHECKED - ACL  
DATE - 06/04/10  
REVISED -  
REVISED -  
REVISED -