SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE I000-2A		
20400800	FURNISHED EXCAVATION	CU YD	80	80		
25000200	SEEDING, CLASS 2	ACRE	0.25	0.25		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10		
25100105	MULCH, METHOD 1	ACRE	0.5	0.5		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	20		
28000400	PERIMETER EROSION BARRIER	FOOT	405	405		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.6	0.6		
40600300	AGGREGATE (PRIME COAT)	TON	3	3		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	42	42		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	170	170		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	360	360		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	160	160		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	992	992		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	114	114		
63300575	REMOVE AND REERECT RAIL ELEMENT OF EXISTING GUARD RAIL	FOOT	300	300		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	608	608		
78300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2700	2700		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1103	1103		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2716	2716		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	900	900		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9		

*Specialty Items

Rev.

FILE NAME = c:\pw_work\PWIDOT\GELINH\d0146285\d876d18-sht-plan.dgn	USER NAME = gelinh	DESIGNED - ___	REVISED - ___
		DRAWN - ___	REVISED - ___
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - ___	REVISED - ___
	PLOT DATE = 3/17/2010	DATE - _____	REVISED - ___

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ | SHEET NO. 1 OF 1 SHEETS | STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
592	121-1RS-2	ST CLAIR	13	3

CONTRACT NO. 76D18

FED. ROAD DIST. NO. _ | ILLINOIS | FED. AID PROJECT