

RESURFACING SCHEDULE

STATION	AGGREGATE PRIME COAT (TON)	BITUMINOUS MATERIAL PRIME COAT (TON)	LEVELING BINDER (TON)	HMA BINDER COURSE MIX "B", N70 (TON)	HMA SURFACE COURSE MIX "D", N70 (TON)	AGGREGATE SHOULDER TYPE B (TON)	REM & REER RAIL ELEM. OF EXISTING GUARD RAIL (FT)	HMA SURFACE REMOVAL BUTT-JOINT (SQ YD)
424+25.00 RT/LT TO 431+00.00 RT/LT	2.84	0.59			159.29			86.67
424+25.00 RT/LT TO 424+55.00 RT/LT						44.80		
424+25.00 RT/LT TO 427+20.00 RT/LT			21.28					
424+25.00 RT/LT TO 426+00.00 RT/LT				22.81				
426+00.00 RT/LT TO 426+75.00 RT/LT			2.91					
426+75.00 RT/LT TO 427+00.00 RT/LT				336.31				
427+00.00 RT/LT TO 429+50.00 RT/LT						54.20		
427+20.00 RT/LT TO 429+22.00 RT/LT							300	
427+50.00 RT/LT TO 429+00.00 RT/LT						14.60		
429+22.00 RT/LT TO 431+00.00 RT/LT			17.52					
429+50.00 RT/LT TO 431+00.00 RT/LT								83.33
430+70.00 RT/LT TO 431+00.00 RT/LT								
TOTAL	2.84	0.59	41.71	359.12	159.29	113.60	300.00	170.00

PAVEMENT MARKING SCHEDULE

STATION	THERMOPLASTIC PVMT MKG			RAISED REFL. PMK MARKERS TWO-WAY (EA)
	4" WHITE LINE (FT)	4" DOUBLE YELLOW LINE (FT)		
424+23.00 LT TO 431+02.00 LT	EDGE LINE	679.00		
424+23.00 RT TO 431+02.00 RT	EDGE LINE	679.00		
424+23.00 CL TO 431+02.00 CL	CENTER LINE		1358.00	9
TOTAL		1358.00	1358.00	9

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 2 (ACRE)	NITROGEN FERT. NUTR (POUND)	PHOSPHORUS FERT. NUTR (POUND)	POTASSIUM FERT. NUTR (POUND)	MULCH METHOD 1 (ACRE)
424+50.00 TO 430+00.00 RT	0.07	6.47	6.47	6.47	0.07
424+50.00 TO 430+50.00 LT	0.04	3.37	3.37	3.37	0.04
TOTAL	0.11	9.84	9.84	9.84	0.11

EARTHWORK SCHEDULE

LOCATION	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
STA 427+00.00 TO STA 429+50.00	77.6	-77.6

MILLING, BINDER, AND SURFACE SCHEDULE

STATION	EXISTING ELEV.	PROPOSED ELEV.	MILLING DEPTH (IN)	SURF THICKNESS (IN)	LEVELING BINDER THICK (IN)	BINDER THICKNESS (IN)
424+25.00	422.51	422.51	2.25	1.5	0.75	
424+50.00	422.66	422.52	3.93	1.5	0.75	
424+75.00	422.64	422.53	3.57	1.5	0.75	
425+00.00	422.67	422.56	3.57	1.5	0.75	
425+25.00	422.65	422.62	2.61	1.5	0.75	
425+50.00	422.71	422.71	2.25	1.5	0.75	
425+75.00	422.75	422.83	1.29	1.5	0.75	
426+00.00	422.80	422.98	0.09	1.5	0.75	
426+25.00	422.87	423.15		1.5		1.86
426+50.00	423.07	423.36		1.5		1.98
426+75.00	423.43	423.6	0.21	1.5	0.75	
427+00.00	423.69	423.84	0.45	1.5	0.75	
427+25.00	423.58	424.06		1.5		4.26
427+50.00	423.51	424.2		1.5		6.78
427+75.00	423.42	424.29		1.5		8.94
428+00.00	423.12	424.31		1.5		12.78
428+25.00	422.98	424.26		1.5		13.86
428+50.00	423.03	424.15		1.5		11.94
428+75.00	423.14	423.98		1.5		8.58
429+00.00	423.01	423.74		1.5		7.26
429+25.00	423.00	423.44		1.5		3.78
429+50.00	423.15	423.08	3.09	1.5	0.75	
429+75.00	422.96	422.65	5.97	1.5	0.75	
430+00.00	422.37	422.16	4.77	1.5	0.75	
430+25.00	421.63	421.61	2.49	1.5	0.75	
430+50.00	420.93	420.99	1.53	1.5	0.75	
430+75.00	420.24	420.34	1.05	1.5	0.75	
431+00.00	419.69	419.69	2.25	1.5	0.75	

TEMPORARY EROSION CONTROL SCHEDULE

LOCATION	RT/LT	TEMP. EROS. CONTROL SEEDING (POUND)	MULCH METHOD 1 (ACRE)	PERIMETER EROSION BARRIER (FOOT)
424+50.00 TO 430+50.00	LT	6.74	0.07	
424+50.00 TO 430+00.00	RT	12.93	0.14	
427+50.00 TO 429+50.00	RT			204
427+50.00 TO 429+50.00	LT			201
TOTAL		19.67	0.22	405

REMOVAL SCHEDULE

STATION	HMA SURF REMOVAL VAR. DEPTH (SQ YD)	RAISED REFL. PVMT. MRK REMOVAL (EA)
424+25.00 TO 431+00.00	9	
424+25.00 TO 426+00.00 RT/LT	505.56	
426+75.00 TO 427+00.00 RT/LT	69.44	
429+50.00 TO 431+00.00 RT/LT	416.67	
TOTAL	991.67	9

TEMPORARY PAVEMENT MARKING SCHEDULE

STATION	TEMP PVMT MARKING LINE 4" (FT)	SHORT TERM PAVEMENT MARKING (FT)	WORK ZONE PAVEMENT REMOVAL (SQ FT)	PAVEMENT MARKING REMOVAL (SQ FT)
424+25.00 TO 431+00.00	EDGE LINES	1350.0	405	135.0
424+25.00 TO 431+00.00	CENTER LINE	1350.0	202.5	67.5
TOTAL		2700.0	607.5	202.5