

PATCHING SCHEDULE

LOCATION	EASTBOUND LANE								WESTBOUND LANE							
	SIZE		PAVEMENT PATCHING 13"			PAVEMENT PATCHING 10"			SIZE		PAVEMENT PATCHING 13"			PAVEMENT PATCHING 10"		
	LENGTH	WIDTH	TYPE II	TYPE III	TYPE IV	TYPE II	TYPE III	TYPE IV	LENGTH	WIDTH	TYPE II	TYPE III	TYPE IV	TYPE II	TYPE III	TYPE IV
MILE STATION	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
1.449	60	5						33.33								
1.461	7	12					9.33									
1.462	223	5						123.89								
1.470									7	12				9.33		
1.471									176	5						97.78
1.504	7	12					9.33		7	12				9.33		
1.505	141	5						78.33	141	5						78.33
1.832									500	4			222.22			
2.019	600	4						266.67								
2.032									100	4						44.44
2.332									200	4			88.89			
2.382									11	6	7.33					
2.432									12	12		16.00				
2.530	12	6	8.00													
2.532									100	4			44.44			
2.732									150	6						100.00
2.832									150	3						50.00
3.332									12	12					16.00	
3.432									12	12					16.00	
3.462									6	12	8.00					
3.630	12	12		16.00												
3.730	12	6	8.00													
3.732									12	12		16.00				
4.130	12	6	8.00													
4.232									6	12	8.00					
4.432									12	12		16.00				
4.532									600	5			333.33			
4.600	700	3			233.33											
4.832									12	6	8.00					
4.932									12	6	8.00					
5.110	12	6	8.00													
5.130	12	6	8.00													
5.432									50	3		16.67				
5.532									12	6	8.00					
5.625	300	3					100.00									
5.932									500	4			222.22			
6.032									700	4						311.11
6.232									12	6				8.00		
6.244	200	3						66.67								
6.330	12	6	8.00													
SUBTOTAL			194.44	126.44	701.89	39.33	16.00	848.00			157.44	105.11	1604.17	48.67	32.00	929.89
ANTICIPATED FAILURE (20%)			38.89	25.29	140.38	7.87	3.20	169.60			31.49	21.02	320.83	9.73	6.40	185.98
TOTAL			233.33	151.73	842.27	47.20	19.20	1017.60			188.93	126.13	1925.00	58.40	38.40	1115.87

FILE NAME =	USER NAME = #USER*	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
#FILE#		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	329	20RS-4120-2,19RS-3	RANDOLPH	19	6
		CHECKED -	REVISED -								CONTRACT NO. 76D36				
		DATE -	REVISED -								FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				