

PAVEMENT MARKING SCHEDULE

LOCATION		THERMOPLASTIC PAVEMENT MARKING - LINE 4"				TEMPORARY PAVEMENT MARKING LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS
		SOLID WHITE EDGE LINE (EDGE LINES)	SKIP DASH (YELLOW)	NO PASSING ZONE (SOLID YELLOW)	SOLID LINE (YELLOW)			
M.S.	TO M.S.	FOOT	FOOT	EB OR WB	FOOT	FOOT	EACH	EACH
0.026	0.143	1235.5		EB/WB	1235.5	2471.0	8	8
0.143	0.241	1034.9	130	WB	517.4	1682.3	6	6
0.241	0.296	580.8		EB/WB	580.8	1161.6	4	4
0.296	0.466	1795.2	220	EB	897.6	2912.8	11	11
0.466	0.656	2006.4		EB/WB	2006.4	4012.8	13	13
0.656	0.865	2207.0	280	WB	1103.5	3590.5	14	14
0.865	1.046	1911.4	240	EB	955.7	3107.1	12	12
1.046	1.369	3410.9		EB/WB	3410.9	6821.8	21	21
1.369	1.588	2312.6	290	WB	1156.3	3758.9	14	14
1.588	1.762	1837.4	230			2067.4	11	11
1.762	1.959	2080.3	260	EB	1040.2	3380.5	13	13
1.959	2.070	1172.2		EB/WB	1172.2	2344.4	7	7
2.070	2.270	2112.0	260	WB	1056.0	3428.0	13	13
2.270	2.514	2576.6	320			2896.6	16	16
2.514	2.732	2302.1	290	EB	1151.0	3743.1	14	14
2.732	2.794	654.7		EB/WB	654.7	1309.4	4	4
2.794	3.028	2471.0	310	WB	1235.5	4016.5	15	15
3.028	3.170	1499.5	190			1689.5	9	9
3.170	3.340	1795.2	220	EB	897.6	2912.8	11	11
3.340	3.368	295.7	40			335.7	2	2
3.368	3.533	1742.4	220	WB	871.2	2833.6	11	11
3.533	3.941	4308.5	540			4848.5	27	27
3.941	4.131	2006.4	250	EB	1003.2	3259.6	13	13
4.131	4.145	147.8	20			167.8	1	1
4.145	4.296	1594.6	200	WB	797.3	2591.9	10	10
4.296	4.345	517.4		EB/WB	517.4	1034.8	3	3
4.345	4.445	1056.0	130	EB	528.0	1714.0	7	7
4.445	4.509	675.8	80			755.8	4	4
4.509	4.615	1119.4	140	WB	559.7	1819.1	7	7
4.615	4.645	316.8		EB/WB	316.8	633.6	2	2
4.645	4.774	1362.2	170	EB	681.1	2213.3	9	9
4.774	4.838	675.8	80			755.8	4	4
4.838	4.973	1425.6	180	WB	712.8	2318.4	9	9
4.973	5.451	5047.7	630			5677.7	32	32
5.451	5.666	2270.4	280	EB	1135.2	3685.6	14	14
5.666	5.741	792.0		EB/WB	792.0	1584.0	5	5
5.741	5.926	1953.6	240	WB	976.8	3170.4	12	12
5.926	6.011	897.6	110			1007.6	6	6
6.011	6.120	1151.0	140	EB	575.5	1866.5	7	7
6.120	6.210	950.4		EB/WB	950.4	1900.8	6	6
6.210	6.409	2101.4	260	WB	1050.7	3412.1	13	13
6.409	6.500	961.0	120			1081.0	6	6
SUBTOTAL		68365.2	7070		30539.4	105974.6	427	427
TOTAL		105974.6				105974.6	427	427

GUARDRAIL SCHEDULE

LOCATION	OFFSET	SPBGR REMOVAL	SPBGR TYPE A	TRAFFIC BARRIER TERMINAL	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL MARKERS, TYPE A
				TYPE 1 SPECIAL		
MILE STATION	RT/LT	FOOT	FOOT	EACH	EACH	EACH
1.979 TO 1.986	RT			1	1	
2.038 TO 2.045	RT			1	1	
4.575 TO 4.584	LT			1	1	
4.575 TO 4.584	RT			1	1	
4.617 TO 4.626	RT			1	1	
4.641 TO 4.650	LT			1	1	
5.200 TO 5.209	RT			1	1	
5.223 TO 5.232	LT			1	1	
5.294 TO 5.303	RT			1	1	
5.317 TO 5.326	LT			1	1	
1.979 TO 2.045	RT	350				
1.986 TO 2.038	RT		275			4
4.575 TO 4.600	LT	84.5				
4.584 TO 4.641	LT		300			5
4.578 TO 4.600	RT	74				
4.584 TO 4.617	RT		175			5
5.253 TO 5.270	RT	95				
5.209 TO 5.294	RT		450			5
5.257 TO 5.276	LT	105				
5.232 TO 5.317	LT		450			5
TOTALS		708.5	1650	10	10	19

FILE NAME =
#FILE#

USER NAME = #USER#

DESIGNED -
DRAWN -

REVISED -
REVISED -

PLOT SCALE = #SCALE#

CHECKED -
DATE -

REVISED -
REVISED -

PLOT DATE = #DATE#

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING SCHEDULE

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
329	20RS-4(20-2,19)RS-3	RANDOLPH	19	7
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 76D36	