SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

URBAN

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: 1000 100% STATE	-------	-------
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.4	1.4		
40600300	AGREGATE (PRIME COAT)	TON	7	7		
40600990	TEMPORARY RAMP	SQ YD	111	111		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	504	504		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4495	4495		
44201371	CLASS C PATCHES, TYPE IV, 11 INCH	SQ YD	2314	2314		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3593	3593		
67100100	MOBILIZATION	L SUM	1	1		
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1920	1920		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7940	7940		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	38	38		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	214	214		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7940	7940		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	38	38		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	89	89		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	89	89		
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	5	5		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	27	27		

*Specialty Items

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: -------	-------	-------

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - ___	REVISED - ___	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES
		DRAWN - ___	REVISED - ___		
	PLOT SCALE = $SCALE$	CHECKED - ___	REVISED - ___		
	PLOT DATE = $DATE$	DATE - _____	REVISED - ___		SCALE: _____ SHEET NO. __ OF ___ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
103	271-4	ST. CLAIR	24	3
		CONTRACT NO. 76D97		

FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT