

RESURFACING					
STATION	HMA SURFACE REMOVAL, 2"	TEMPORARY RAMPS	POLY HMA SURFACE COURSE, MIX D, N70	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)
	SQ YD	SQ YD	TON	TON	TON
NB 364+10 - 390+30	3233.3	17.9	362.1	4.9	1.01
NB 393+00 - 395+30	357.8	18.6	40.1	0.5	0.11
SB 395+25 - 397+50	303.3	18.6	34.0	0.5	0.14
NB 397+90 - 398+90	133.3	18.6	14.9	0.2	0.05
SB 401+61 - 403+36	233.4	18.6	26.1	0.4	0.07
NB 401+18 - 402+93	233.3	18.6	26.2	0.4	0.07
TOTALS	4494.4	110.9	503.4	6.9	1.40

PATCHING SCHEDULE				
STA. TO STA.	LENGTH	WIDTH	CLASS C, TYPE IV, 11"	STRIP REFLEC. CRACK CONTROL TREATMENT
	FEET	FEET	SQ YD	FOOT
NB 364+10 - 390+30	2620	6	1746.7	2632
NB 393+00 - 395+30	230	6	153.3	242
SB 395+25 - 397+50	225	6	125.0	235
NB 397+90 - 398+90	100	6	55.6	110
SB 401+61 - 403+36	175	6	116.7	187
NB 401+18 - 402+93	175	6	116.7	187
TOTALS			2314.0	3593

PAVEMENT MARKING SCHEDULE											
STATION	LENGTH	SHORT-TERM PAVEMENT MARKING (2 APPS)	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
	FEET	FEET	SQ FT	FEET	FEET	FEET	FEET	FEET	FEET	EACH	EACH
NB 364+10 - 390+30	2620	960	160.0	3333	3333	37.3	37.3	12	12	66	66
NB 393+00 - 395+30	230	80	13.3	290	290					6	6
SB 395+25 - 397+50	225	80	13.3	285	285					6	6
NB 397+90 - 398+90	100	32	5.3	130	130					3	3
SB 401+61 - 403+36	175	64	10.7	215	215					4	4
NB 401+18 - 402+93	175	64	10.7	215	215					4	4
TOTALS	3525	1280	213.3	4468	4468	37.3	37.3	12	12	89	89

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - ---	REVISED - ---					103	271-4	ST. CLAIR	24	4
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---		SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 76D97				
	PLOT DATE = #DATE#	DATE - -----	REVISED - ---		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT							