

SUMMARY OF QUANTITIES

80% FED. / 20% STATE

SUMMARY OF QUANTITIES

RESURFACING	
WILLIAMSON COUNTY	
CONSTRUCTION TYPE CODE 1000	
FAP 331 (IL 13 WBL)	FAP 331 (IL 13 EBL)

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
X0322729	MATERIAL TRANSFER DEVICE	TON	31643	17019	14624
Z0017100	DOWEL BARS	EACH	580		580
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	51548.4	27930.3	23618.1
40600300	AGGREGATE (PRIME COAT)	TON	859.3	465.6	393.7
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	12645	6797	5848
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3686	1588	2098
40600990	TEMPORARY RAMP	SQ YD	143	73	70
40603545	POLYMER ^{IZED} HOT-MIX ASPHALT SURFACE COURSE, MIXTURE 'D', N90	TON	18998	10222	8776
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	220	94	126
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	184591	115782	68809
44200517	CLASS A PATCHES, TYPE II, 7 INCH	SQ YD	137		137
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	124		124
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	200		200
44213000	PATCHING REINFORCEMENT	SQ YD	137		137
44213200	SAW CUTS	FOOT	1106		1106
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3979	2077	1902
48203100	HOT-MIX ASPHALT SHOULDERS	TON	14389	7872	6517
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1.5	1.5
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.5	0.5
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	2	2
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	15326	8429	6897