

**IL 13 EASTBOUND PAVEMENT MARKING SCHEDULE**

(CONTINUED)

STATION TO STATION				PERFORMED PLASTIC PAVEMENT MARKING, TY. B					TEMPORARY PAVEMENT MARKING				SHORT-TERM	NOTES	
				LEFT 4 INCH YELLOW (EDGE LINE)	RIGHT 4 INCH WHITE (EDGE LINE)	4 INCH WHITE (TURN LANE)	5 INCH (SKIP-DASH)	24 INCH (STOP BAR)	LETTERS AND SYMBOLS	4 INCH	5 INCH	24 INCH	LETTERS AND SYMBOLS		5 INCH
				FOOT		FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	SO FT		FOOT
<b>Intersection of IL 166 - Sta. 100+44</b>															
	100+44.0	TO	341+00.0				6,014				6,014		2,887		
RT	100+44.0							12						STOP BAR	
RT	100+74.0							20			20			RTL STOP BAR	
LT	100+73.0	TO	153+75.0	5302									212	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	101+45.0	TO	157+57.0		5612								200	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	151+47.0	TO	157+57.0			610							73	RTL @ DAVIS PRAIRIE RD.	
RT	151+57.0								20.8				20.8	ONLY	
RT	151+85.0								15.6				15.6	RIGHT TURN ARROW	
RT	154+02.0							12			12				
LT	154+70.0	TO	180+20.0	2550									102	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	154+51.0	TO	203+10.0		4,859								185	DIAGONALS ON SHLD. (SEE NOTE 1)	
LT	177+80.0	TO	180+20.0			240							29	LTL @ STILLEY'S MILL RD.	
LT	177+90.0								20.8				20.8	ONLY	
LT	178+18.0								15.6				15.6	LEFT TURN ARROW	
LT	181+80.0	TO	203+24.0	2,144									86	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	199+97.0	TO	203+24.0			327							39	RTL @ W. CRAB ORCHARD RD.	
RT	200+00.0								20.8				20.8	ONLY	
RT	200+28.0								15.6				15.6	RIGHT TURN ARROW	
RT	204+00.0							12					12		
RT	204+30.0							20			20				
LT	204+70.0	TO	239+34.0	3,464									139	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	205+44.0	TO	239+78.0		3,434								129	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	237+73.0	TO	239+95.0			222							27	RTL @ BARBARA KAY RD.	
RT	237+83.0								20.8				20.8	ONLY	
RT	238+11.0								15.6				15.6	RIGHT TURN ARROW	
RT	240+00.0							27			27				
LT	240+97.0	TO	264+58.0	2,361									94	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	239+97.0	TO	264+30.0		2,433								82	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	261+04.0	TO	265+00.0			396							48	RTL @ PAULTON RD.	
RT	261+14.0								20.8				20.8	ONLY	
RT	261+42.0								15.6				15.6	RIGHT TURN ARROW	
LT	261+58.0	TO	265+00.0			342							41	LTL @ PAULTON RD.	
LT	261+68.0								20.8				20.8	ONLY	
LT	261+96.0								15.6				15.6	LEFT TURN ARROW	
RT	265+34.0							12					12		
RT	265+63.0							22			22				
LT	266+00.0	TO	294+75.0	2,875									115	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	266+80.0	TO	294+57.0		2,777								100	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	292+38.0	TO	295+30.0			292							35	RTL @ E. CRAB ORCHARD RD.	
RT	292+48.0								20.8				20.8	ONLY	
RT	292+76.0								15.6				15.6	RIGHT TURN ARROW	
RT	295+50.0							12					12		
RT	295+90.0							22			22				
LT	296+25.0	TO	341+00.0	4,475									179	DIAGONALS ON SHLD. (SEE NOTE 1)	
RT	296+44.0	TO	341+00.0		4,456								178	DIAGONALS ON SHLD. (SEE NOTE 1)	
<b>SUBTOTALS</b>				<b>32,801</b>	<b>33,763</b>	<b>4079</b>	<b>8802</b>	<b>257</b>	<b>436.8</b>	<b>70,643</b>	<b>8,802</b>	<b>257</b>	<b>436.8</b>	<b>6,897</b>	
<b>IL 13 EBL TOTALS</b>				<b>70,643</b>			<b>8802</b>	<b>257</b>	<b>436.8</b>	<b>70,643</b>	<b>8,802</b>	<b>257</b>	<b>436.8</b>	<b>6,897</b>	

NOTE 1: QUANTITY UNDER SHORT-TERM PAVEMENT MARKING.

\* (6-1)RS-216-3,6-2,7-1,7-3)RS-1

FILE NAME #	USER NAME # macordkr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE - IL 13 WBL HMA AND AGGREGATE SHOULDERS</b>	F.A.P. RTE. #	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
al\pv_work\pavdot\macordkr\d0186822\sh	plnpr.f.dgn	DRAWN -	REVISED -			331	*	WILLIAMSON	27	16
PLOT SCALE = 1/8" = 100.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 78190				
PLOT DATE = 4/15/2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				
SCALE: _____		SHEET NO. _____ OF _____ SHEETS		STA. _____ TO STA. _____						