

LOCATION 2 PAVEMENT MARKING SCHEDULE

STATION TO STATION				PAINT PAVEMENT MARKING			THERMOPLASTIC PAVEMENT MARKING	TEMPORARY		SHORT-TERM	NOTES
				4 INCH WHITE (EDGE LINE)	4 INCH YELLOW (NO PASS ZONE)	4 INCH (SKIP-DASH)	24 INCH (STOP BAR) (SEE NOTE 1)	4 INCH	24 INCH	4 INCH	
				FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
MAINLINE: Sta. 195+00 to Sta. 434+55											
LT	195+00.0	TO	244+77.0	4977				4977			
RT	195+00.0	TO	244+77.0	4977				4977			
	195+00.0	TO	244+77.0			1244		1244		597	
	249+90.0	TO	266+69.6			420		420		202	
RT	237+03.0	TO	244+77.0		774			774			
LT	226+60.0	Otter Slough Rd.					12		12		
RT	226+60.0	Otter Slough Rd.					12		12		
SN 039-0048 Omission - Sta. 244+77 to Sta. 249+50											
LT	249+50.0	TO	266+69.6	1720				1720			
RT	249+50.0	TO	266+69.6	1520				1,520			
	283+92.2	TO	327+37.0			1,086		1,086		521	
LT	249+90.0	TO	259+63.0		973			973			
RT	253+00.0	Gorham Rd.					40		40	Thru Ln & Turn Ln. - 20' Each	
EQ. Sta. 266+69.6 (bk.) = Sta. 283+92.9 (ah.)											
LT	283+92.9	TO	327+37.0	4344				4,344			
RT	283+92.9	TO	327+37.0	4344				4,344			
RT	322+35.0	TO	327+37.0		502			502			
		TO									
SN 039-0067 Omission - Sta. 327+37 to Sta. 333+96											
LT	333+96.0	TO	434+55.0	9943				9,943			
RT	333+96.0	TO	434+55.0	10059				10,059			
	333+96.0	TO	358+46.0			613		613		294	
	363+69.0	TO	373+40.0			243		243		117	
	374+46.0	TO	434+55.0			1,502		1,502		721	
LT	369+08.0	Oakwoods Bottoms Rd.					12		12		
LT	333+96.0	TO	338+71.0		475			475			
RT	347+37.0	TO	363+69.0		1,632			1,632			
LT	358+46.0	TO	374+46.0		1,600			1,600			
RT	373+40.0	TO	380+06.0		666			666			
LT	384+81.0	TO	390+36.0		555			555			
RT	433+76.0	TO	434+55.0		79			79			
SUB-TOTALS				41,883	7,256	5,108	76	54,247	76	2,452	
TOTALS					54,247		76	54,247	76	2,452	

NOTE 1 : STOP BARS SHALL BE PLACED 10 FEET BACK FROM EDGE OF PAVEMENT OR AS DIRECTED BY THE ENGINEER.