

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF REMOVAL OF THE EXISTING BRIDGE, CONSTRUCTION OF A DOUBLE-BARREL PRE-CAST BOX CULVERT WITH CAST-IN-PLACE END SECTIONS, SOLDIER PILE RETAINING WALLS, CONSTRUCTION OF PCC PAVEMENT, AGGREGATE SHOULDER, GUARDRAIL, AND ALL OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

ALL ELEVATIONS SHOWN IN PLANS ARE BASED ON U.S.G.S. DATUM. BENCHMARK IS LOCATED ON TOP OF EXISTING WINGWALL AT THE NORTHEAST CORNER. ELEVATION IS 438.08.

THE EXISTING ET-2000 GUARDRAIL TERMINALS SHALL REMAIN THE PROPERTY OF IDOT AND SHALL BE DELIVERED TO THE OPERATIONS YARD SOUTH OF OLNEY.

USE POROUS GRANULAR EMBANKMENT, RIPRAP, AND/OR AGGREGATE SHOULDER TO BACKFILL AROUND NEW WINGWALLS INSTEAD OF SOIL. THIS WILL PREVENT EROSION AND ELIMINATE THE NEED FOR SEEDING.

THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS AND MUST BE CONSIDERED APPROXIMATE. FIELD MARKINGS OF FACILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

INDEX OF SHEETS

SHEET NO	TITLE
1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5	SCHEDULES & DETAILS
6	PLAN AND PROFILE SHEET
7-8	DETOUR PLAN
9-13	CULVERT SN 080-2005 DETAILS
14	BORING LOGS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
420001-07	PAVEMENT JOINTS
420601-05	7.2 M (24') PCC PAVEMENT
420701-02	PAVEMENT FABRIC
515001-03	NAME PLATE FOR BRIDGES
630001-08	STEEL PLATE BEAM GUARDRAIL
630101-08	GUARDRAIL MOUNTED ON EXISTING CULVERTS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006-03	OFF-ROAD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011-02	OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701311-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
BLR-21-3	TYP. APPL. OF T.C.D. FOR CONST. ON RURAL LOCAL HIGHWAYS

701301-03

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & INDEX OF SHEETS			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
g:\pw_work\PWIDOT\TEASLEYCK\desf60131\dwg\4992-shf-gennotes.dgn		DRAWN -	REVISED -		1720	5B-1	Richland	14	2			
PLOT SCALE = 50.0000 "/ IN.		CHECKED -	REVISED -		CONTRACT NO. 94992							
PLOT DATE = 1/13/2010		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							
				SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.			