

SUBBASE GRANULAR MATERIAL, TYPE C 10"			
STATION TO	STATION	LOCATION	SQ YD
PARKING LOT AND DRIVEWAY			702
TOTAL			702

BITUMINOUS MATERIALS (PRIME COAT)			
LOCATION			GALLON
OVER ALL SUBBASE GRAN MATL			3922
TOTAL			3922

AGGREGATE (PRIME COAT)			
LOCATION			TON
AS DIRECTED BY THE ENGINEER			16
TOTAL			16

HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50			
LOCATION			TON
PARKING LOT AND DRIVEWAY			77
TOTAL			77

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50				
STATION TO	STATION	LOCATION		TON
100+00	136+14.41	MAIN LINE		693
PARKING LOT AND DRIVEWAY				77
136+37.01	150+06.38	MAIN LINE		240
151+41.41	165+18.91	MAIN LINE		353
165+18.91	176+50	MAIN LINE		463
176+50	177+06	MAIN LINE		15
177+06	204+00	MAIN LINE		517
204+00	208+30	MAIN LINE		110
30+05	40+91.96	SPUR		209
TOTAL				2677

INCIDENTAL HOT-MIX ASPHALT SURFACING			
STATION TO	STATION	LOCATION	TON
100+00		LT&RT RADII	2
102+42.14		LT TO PARKING	14
108+11.90		LT RADII	2
121+75		LT RADII	2
136+14.41		LT&RT RADII	2
136+37.01		LT&RT RADII	2
153+50		LT	6
165+27.34		LT	9
170+13		LT	13
172+00		LT	17
172+50		RT	38
173+00		LT	28
176+75		LT	16
198+00		LT	6
204+25		LT	8
207+25		LT	4
207+89.20		LT BIKEPATH	7
35+38.19		RT	4
35+76.19		LT	1
TOTAL			181

SIGN PANEL, TYPE 1 SPECIAL				
STATION	TYPE	LOCATION		SQ FT
98+80	D11-1, M7-1L	CL		3.75
100+10	D11-1, M7-1R	RT		3.75
100+18	R5-3	RT		4.00
100+18	R1-1	LT		2.25
101+50	W3-1A	LT		2.25
102+29	R1-2	LT		2.00
102+20	R7-8, R7-1101	LT		2.50
107+60	RG-100L	RT		3.50
107+93	R1-1	LT		2.25
108+57	RG-100R	LT		3.50
36+35	R5-3	LT		4.00
36+43	R1-1	LT		2.25
121+21	RG-100L	RT		3.50
121+63	R1-1	LT		2.25
122+35	RG-100R	LT		3.50
133+88	W11-1	LT		6.25
135+19	W3-1A	RT		2.25
136+12	R1-1	RT		2.25
136+12	R5-3	LT		4.00
136+47	W11-1, W16-7	RT		8.25
136+52	R5-3	RT		4.00
136+52	R1-1	LT		2.25
137+25	W3-1A	LT		2.25
172+60	W11-1, W16-7	RT		8.25
203+98	R1-1	LT		2.25
207+69	D11-1, M7-1L	RT		3.75
207+78	D11-1, M7-1R	RT		3.75
208+20	R5-3	LT		4.00
TOTAL				98.75

THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS			
LOCATIONS			SQ FT
PARKING LOT			4.60
TOTAL			4.60

THERMOPLASTIC PAVEMENT MARKING - LINE 4"			
STATION TO	STATION	LOCATION	FOOT
YELLOW			
100+15	102+00	CENTER SOLID	185
102+00	135+00	CENTER DASH	825
135+00	136+14.41	CENTER SOLID	115
136+37.01	137+50	CENTER SOLID	113
137+50	150+06.38	CENTER DASH	315
151+41.41	164+16	CENTER DASH	319
177+00	208+30	CENTER DASH	783
30+20	40+71.96	CENTER DASH	263
WHITE			
164+16	177+00	LT&RT EDGES	2568
PARKING LOT			PARKING LINES
TOTAL			5749

THERMOPLASTIC PAVEMENT MARKING - LINE 12"			
STATION TO	STATION	LOCATION	FOOT
RIVERVIEW ROAD CROSSING - LT & RT EDGE			46
RIVERVIEW ROAD CROSSING - DIAGONAL			60
TOTAL			106

THERMOPLASTIC PAVEMENT MARKING - LINE 24"			
STATION TO	STATION	LOCATION	FOOT
100+15		STOP BAR	5
136+04.41		STOP BAR	5
136+37.07		STOP BAR	5
208+30		STOP BAR	5
30+10		STOP BAR	9
36+55.96		LT STOP BAR	9
40+81.96		STOP BAR	9
TOTAL			47

FENCE REMOVAL			
STATION TO	STATION	LOCATION	FOOT
100+28		AT PATH	35
PARKING LOT			WEST SIDE
136+75		AT PATH	20
TOTAL			191

WOOD POST AND RAIL FENCE			
STATION TO	STATION	LOCATION	FOOT
PARKING AREA			354
BRIDGE		N&S APP PVT	78
178+28	180+63	20' LT	232
178+33		LT	16
178+33		RT	13
TOTAL			693

GATE REMOVAL			
STATION TO	STATION	LOCATION	EACH
135+71		AT PATH	1
178+33		AT PATH	1
TOTAL			2

SEEDING, SPECIAL			SQ YD
LOCATION			
WITHIN CONSTRUCTION LIMITS FROM			7050
100+00 TO 135+71 (USF&W PRAIRIE)			
MAINLINE FROM 135+71 TO 164+14			3159
MAINLINE FROM 183+14 TO 208+30			2796
TOTAL			13005

VEHICLE CONTROL BOLLARDS			
STATION		LOCATION	EACH
100+28			1
102+42.14		22' LT	1
135+71			1
136+75			1
164+16			1
178+33			1
204+00			1
36+46.46		54' LT	1
TOTAL			8

WOOD GATE ASSEMBLY SPECIAL			
STATION		LOCATION	EACH
153+39		LT	1
TOTAL			1