



BILL OF MATERIAL

LOCATION	ITEM	UNIT	TOTAL
25B	Chain Link Fence, 42" Attached to Structure (Special)	FOOT	1,395
25C	Chain Link Fence, 42" Attached to Structure (Special)	FOOT	953
25D	Chain Link Fence, 42" Attached to Structure (Special)	FOOT	2,076
25E	Chain Link Fence, 42" Attached to Structure (Special)	FOOT	985
Total		FOOT	5,409

NOTES:

- The Contractor shall drill and epoxy grout 5/8" diameter anchor rods. The Contractor shall use the capsule or the adhesive cartridge type anchor rods that have been previously tested and given prior approval by the Department for the above specified anchor rod spacing. The Contractor shall install these anchor rods in pre-drilled holes according to the manufacturer's recommendations and procedures. The capsule or adhesive cartridge shall be sealed with pre-measured amounts of adhesive chemical. Anchor rod threading to be peened after nuts are installed.
- For additional chain link fence details, see Standard 664001.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)
CHAIN LINK FENCE, 42" ATTACHED TO STRUCTURE (SPECIAL) DETAILS
 S.N. DESIGNED BY: MAF
 SCALE: N.T.S. DRAWN BY: MAF
 DATE: FEBRUARY 13, 2009 CHECKED BY: MI

PA 02573 Voadac 33N W 33d r/s1013 adg9 3/19/2009 10:43:33 AM