

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) I-11	WILL	176	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

URBAN  
90% F.F.D.  
10% STATE

SPEC. ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		STRUCT.	SIGNING
					1000	Y220		
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2454	2454			
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	740	740			
*	20101100	TREE TRUNK PROTECTION	EACH	5	5			
*	20101200	TREE ROOT PRUNING	EACH	5	5			
*	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	50	50			
*	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	22	22			
	20200100	EARTH EXCAVATION	CU YD	215	215			
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	7200	7200			
	20400800	FURNISHED EXCAVATION	CU YD	8625	8625			
	20800150	TRENCH BACKFILL	CU YD	10	10			
*	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	28472	28472			
*	21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	4211	4211			
*	25000210	SEEDING, CLASS 2A	ACRE	1.75	1.75			
*	25000310	SEEDING, CLASS 4	ACRE	4	4			
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	158	158			
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	158	158			
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	158	158			
*	25100115	MULCH, METHOD 2	ACRE	5.75	5.75			
*	25100630	EROSION CONTROL BLANKET	SQ YD	27830	27830			
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	575	575			
	28000300	TEMPORARY DITCH CHECKS	EACH	53	53			
	28000510	INLET FILTERS	EACH	93	93			
	28100105	STONE RIPRAP, CLASS A3	SQ YD	778	778			
	31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1483	1483			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	924	924			
	44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	75	75			
	44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	740	740			
	48203012	HOT-MIX ASPHALT SHOULDERS, 3 3/4"	SQ YD	1483	1483			
	50300225	CONCRETE STRUCTURES	CU YD	28.2		28.2		
	50300300	PROTECTIVE COAT	SQ YD	77.5		77.5		
	50800105	REINFORCEMENT BARS	POUND	4180		3720	460	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	5250		5250		
	51602000	PERMANENT CASING	FOOT	54.8		54.8		
*	51603000	DRILLED SHAFT IN SOIL	CU YD	14.4		14.4		
*	51604000	DRILLED SHAFT IN ROCK	CU YD	2.9		2.9		

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 55 (BLACK ROAD TO U.S. ROUTE 30)  
NOISE ABATEMENT WALLS

**SUMMARY OF QUANTITIES**  
I

SCALE: N.T.S. DRAWN BY AG  
DATE: 02/06/09 CHECKED BY DDH

**TENG** TENG & ASSOCIATES, INC.  
ENGINEERS/ARCHITECTS/PLANNERS  
CHICAGO, ILLINOIS