

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) 1-12	WILL	147	4
STA. 610+25.64		TO STA. 767+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
	SQO-01 OF 3			

SUMMARY OF QUANTITIES					90% FED/10% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				NOISE WALL		100% State Non-Participating	
				Sta.610+25.64 to Sta. 767+00.00	Sta.610+25.64 to Sta. 767+00.00		
				I000	Y220		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	923	923			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	275	275			
20101100	TREE TRUNK PROTECTION	EACH	6	6			
20101200	TREE ROOT PRUNING	EACH	6	6			
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	2	2			
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	4	4			
20200100	EARTH EXCAVATION	CU YD	2,200	2,200			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3,510	3,510			
20800150	TRENCH BACKFILL	CU YD	15.5	15.5			
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	21,060	21,060			
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQYD	1,540	1,540			
* 25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75			
* 25000310	SEEDING, CLASS 4	ACRE	3.25	3.25			
* 25100115	MULCH, METHOD 2	ACRE	4.50	4.50			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	72			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72	72			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72	72			
* 25100630	EROSION CONTROL BLANKET	SQ. YD	21,458	21,458			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	399	399			
28000300	TEMPORARY DITCH CHECKS	EACH	28	28			
28000510	INLET FILTERS	EACH	21	21			
28100105	STONE RIPRAP, CLASS A3	SQ YD	234	234			
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	4,785	4,785			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.2	5.2			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,446	1,446			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	482	482			
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ.YD	674	674			
50300300	PROTECTIVE COAT	SQ.YD	6,598	6,598			
* 51604000	DRILLED SHAFT IN ROCK	CU YD	184		184		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	10	10			
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	9	9			
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	66	66			
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	163	163			
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	75	75			
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	123	123			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	5913	5913			
60109582	PIPE UNDERDRAINS FOR STRUCTURES 6"	FOOT	6127	6127			
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	15	15			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	25.0	25.0			

*Specialty Items



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 US 30 (PLAINFIELD ROAD) TO WEBER ROAD

SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: 2-06-09

DRAWN BY: MMS
 CHECKED BY: DM