

| BITUMINOUS SIDEWALK REMOVAL (XX003669) | | | | | | | | | |
|--|--------|----|-------|----|----------|--------|----|-------|---------|
| STA | OFFSET | | WIDTH | TO | STA | OFFSET | | WIDTH | AREA SY |
| 17+57.25 | 43.30 | RT | 0.1 | | 18+49.27 | 37.00 | RT | 8.3 | |
| 18+49.27 | 37.00 | RT | 8.3 | | 18+65.57 | 33.90 | RT | 5.4 | 91 |
| 17+80.03 | 36.00 | LT | 0.1 | | 18+10.00 | 36.00 | LT | 6.20 | |
| 18+10.00 | 36.00 | LT | 6.20 | | 18+65.53 | 33.00 | LT | 4.4 | 50 |
| 21+35.05 | 33.00 | RT | 4.5 | | 21+87.15 | 33.70 | RT | 5.00 | |
| 21+87.15 | 33.70 | RT | 5.00 | | 22+17.96 | 33.90 | RT | 0.10 | 42 |
| 21+34.64 | 33.00 | LT | 4.5 | | 21+48.48 | 35.70 | LT | 7.50 | |
| 21+48.48 | 35.70 | LT | 7.50 | | 22+18.44 | 40.88 | LT | 7.50 | |
| 22+18.44 | 40.88 | LT | 7.50 | | 22+36.22 | 43.70 | LT | 2.60 | 78 |
| TOTAL | | | | | | | | | 261 |

| COMBINATION CURB AND GUTTER REMOVAL (44000500) | | | | | | | |
|--|--------|----|----|----------|--------|----|-----------|
| STA | OFFSET | | TO | STA | OFFSET | | LENGTH FT |
| 17+54.15 | 43 | RT | | 18+64.13 | 26.00 | RT | 116 |
| 17+65.79 | 45.3 | LT | | 18+65.66 | 33.00 | LT | 104 |
| 21+35.06 | 28.4 | RT | | 22+36.25 | 46.90 | RT | 107 |
| 21+34.57 | 27.9 | LT | | 22+44.32 | 46.09 | LT | 114 |
| TOTAL | | | | | | | 441 |

| GUARDRAIL REMOVAL (63200310) | | | | | | | |
|------------------------------|--------|----|----|----------|--------|----|-----------|
| STA | OFFSET | | TO | STA | OFFSET | | LENGTH FT |
| 17+61.82 | 39.12 | RT | | 18+72.85 | 33.03 | RT | 112 |
| 21+27.33 | 33.3 | LT | | 22+32.04 | 40.00 | LT | 106 |
| TOTAL | | | | | | | 218 |

| PAVEMENT REMOVAL (44000100) | | | | | | |
|---|----|-------|----------|----|-------|---------|
| STA | | WIDTH | STA | | WIDTH | AREA SY |
| 17+50.00 | RT | 30.7 | 18+32.60 | RT | 24 | |
| 18+32.60 | RT | 24 | 18+64.07 | RT | 24 | 335 |
| 17+50.00 | LT | 30 | 18+18.70 | LT | 24 | |
| 18+18.70 | LT | 24 | 18+64.06 | LT | 24 | 327 |
| 21+35.95 | RT | 26 | 22+00.00 | RT | 26 | |
| 22+00.00 | RT | 26 | 22+50.00 | RT | 31.3 | 344 |
| 21+35.95 | LT | 24 | 21+56.69 | LT | 24 | |
| 21+56.69 | LT | 24 | 22+50.00 | LT | 31.2 | 342 |
| ITEMS USED DURING MOT SEE ITEM 40800050 AND SEE ITEM X0712400 | | | | | | 1580 |
| TOTAL | | | | | | 2928 |

| HOT-MIX ASPHALT SURFACE REMOVAL, 3" (44000161) | | | | | | |
|--|----|-------|----------|----|-------|---------|
| STA | | WIDTH | STA | | WIDTH | AREA SY |
| 17+50.00 | RT | 30.7 | 18+32.60 | RT | 24 | |
| 18+32.60 | RT | 24 | 18+64.07 | RT | 24 | 335 |
| 17+50.00 | LT | 30 | 18+18.70 | LT | 24 | |
| 18+18.70 | LT | 24 | 18+64.06 | LT | 24 | 327 |
| 21+35.95 | RT | 26 | 22+00.00 | RT | 26 | |
| 22+00.00 | RT | 26 | 22+50.00 | RT | 31.3 | 344 |
| 21+35.95 | LT | 24 | 21+56.69 | LT | 24 | |
| 21+56.69 | LT | 24 | 22+50.00 | LT | 31.2 | 342 |
| TOTAL | | | | | | 1348 |

| PAVED SHOULDER REMOVAL (44004250) | | | | | | |
|-----------------------------------|----|-------|----------|----|-------|---------|
| STA | | WIDTH | STA | | WIDTH | AREA SY |
| 17+50.00 | RT | 6.6 | 17+61.63 | RT | 6.6 | 7 |
| 17+50.00 | LT | 6.5 | 17+73.00 | LT | 6.5 | |
| 17+73.00 | LT | 6.5 | 18+00.00 | LT | 0.1 | 30 |
| 22+27.60 | RT | 6.5 | 22+50.00 | RT | 6.1 | 16 |
| 22+37.00 | LT | 5.2 | 22+50.00 | LT | 5.4 | 7 |
| TOTAL | | | | | | 60 |

| AGGREGATE SHOULDERS, TYPE B 6" (48101500) | | | | | | | | | |
|---|--------|---------|-------|----|-------------|--------|---------|-------|---------|
| STA | OFFSET | | WIDTH | TO | STA | OFFSET | | WIDTH | AREA SY |
| 17+10.74 | 42.24 | RT | 0 | | 17+39.96 | 44.53 | RT | 4.55 | |
| 17+39.96 | 44.53 | RT | 4.55 | | 17+92.29 | 40 | RT | 4 | |
| 17+92.29 | 40 | RT | 2.76 | | 18+33.06 | 35.26 | RT | 2.76 | |
| 18+33.06 | 35.26 | RT | 2.76 | | 18+65.29 | 36.62 | RT | 2.76 | 57 |
| 17+39.00 | 43.64 | LT | 2.76 | | 18+65.08 | 35.26 | LT | 2.76 | 39 |
| 21+32.48 | 36.7 | RT | 2.76 | | 22+49.33 | 43.3 | RT | 2.76 | 36 |
| 21+35.15 | 36.4 | LT | 2.76 | | 21+59.66 | 35.95 | LT | 2.76 | |
| 21+59.66 | 35.95 | LT | 2.76 | | 22+45.40 | 42.33 | LT | 2.76 | |
| 22+45.40 | 42.33 | LT | 2.76 | | 2249.9342.4 | 44.1 | LT | 2.76 | |
| 2249.9342.4 | 44.1 | LT | 2.76 | | 22+49.93 | 42.4 | LT | 2.76 | |
| 22+49.93 | 42.4 | LT | 2.76 | | 22+57.28 | 45.1 | LT | 4 | |
| 22+57.28 | 45.1 | LT | 4 | | 22+99.65 | 46.45 | LT | 4 | 57 |
| 22+99.65 | 46.45 | LT | 4 | | 23+28.43 | 45.782 | LT | 0 | 13 |
| 17+10.74 | | LT & RT | 1:1 | | 18+65.29 | | LT & RT | 1:1 | 9 |
| 21+35.15 | | LT & RT | 1:1 | | 23+28.48 | | LT & RT | 1:1 | 11 |
| TOTAL | | | | | | | | | 222 |

| HOT MIX ASPHALT PAVEMENT (FULL DEPTH), 15 3/4" (40701996) | | | | | | | |
|---|---------|-------|----|----------|---------|---------|-----|
| STA | | WIDTH | TO | STA | | AREA SY | |
| 17+50.00 | RT | 30.7 | | 18+32.67 | RT | 24 | |
| 18+32.67 | RT | 24 | | 18+57.24 | RT | 24 | 317 |
| 17+50.00 | LT | 30 | | 18+18.70 | LT | 24 | |
| 18+18.70 | LT | 24 | | 18+57.16 | LT | 24 | 309 |
| 21+43.00 | RT | 24 | | 21+85.45 | RT | 24 | |
| 21+85.45 | RT | 24 | | 22+50.00 | RT | 31.3 | 312 |
| 21+43.13 | LT | 24 | | 21+59.93 | LT | 24 | |
| 21+59.93 | LT | 24 | | 22+50.00 | LT | 31.2 | 321 |
| 17+50.00 | LT & RT | 1:1 | | 18+57.17 | LT & RT | 1:1 | 16 |
| 21+43.07 | LT & RT | 1:1 | | 22+50.00 | LT & RT | 1:1 | 16 |
| TOTAL | | | | | | 1291 | |

| HOT MIX ASPHALT SHOULDER, 8" (48203029) | | | | | | | |
|---|---------|-------|----|----------|---------|---------|----|
| STA | | WIDTH | TO | STA | | AREA SY | |
| 17+50.00 | RT | 6.5 | | 17+55.00 | RT | 6.5 | |
| 17+55.00 | RT | 6.5 | | 18+32.67 | RT | 6.5 | |
| 18+32.67 | RT | 6.5 | | 18+57.25 | RT | 6.5 | 78 |
| 17+50.00 | LT | 6.5 | | 18+57.10 | LT | 6.5 | 78 |
| 21+43.04 | RT | 6.5 | | 22+50.00 | RT | 6.5 | 78 |
| 21+43.05 | LT | 6.5 | | 22+30.00 | LT | 6.5 | |
| 22+30.00 | LT | 6.5 | | 22+50.00 | LT | 5.4 | 76 |
| 17+50.00 | LT & RT | 1:1 | | 18+57.17 | LT & RT | 1:1 | 8 |
| 21+43.07 | LT & RT | 1:1 | | 22+50.00 | LT & RT | 1:1 | 8 |
| TOTAL | | | | | | 326 | |

| AGGREGATE SUBGRADE 12" (Z0001050) | | | | | | |
|-----------------------------------|----|-------|----------|----|-------|---------|
| STA | | WIDTH | STA | | WIDTH | AREA SY |
| 17+50.00 | RT | 2 | 18+57.24 | RT | 2 | 24 |
| 17+50.00 | LT | 2 | 18+57.24 | LT | 2 | 24 |
| 21+42.98 | RT | 2 | 22+50.00 | RT | 2 | 24 |
| 21+43.15 | LT | 2 | 22+50.00 | LT | 2 | 24 |
| SEE ITEM 40701996 | | | | | | 1291 |
| SEE ITEM 48203029 | | | | | | 326 |
| TOTAL | | | | | | 1712 |

| HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT (40600982) | | | | |
|---|-------|----------|-------|------------|
| STA | WIDTH | STA | WIDTH | AREA SQ YD |
| 17+30.00 | 79.6 | 17+50.00 | 77.2 | 140 |
| 22+50.00 | 79.6 | 22+70.00 | 77.2 | 125 |
| TOTAL | | | | 266 |

| HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 (40603340) | | | | | | | |
|---|-------|----------|-------|------------|------|------------------|-----|
| STA | WIDTH | STA | WIDTH | AREA SQ YD | RATE | THICKNESS Inches | TON |
| 17+30.00 | 79.6 | 17+50.00 | 77.2 | 140.4 | 112 | 4.5 | 35 |
| 22+50.00 | 79.6 | 22+70.00 | 77.2 | 125.2 | 112 | 4.5 | 32 |
| TOTAL | | | | | | | 67 |

| STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS (63000001) | | | | | |
|--|----|----|----------|----|-------------|
| STA | | TO | STA | | LENGTH FOOT |
| 17+99.46 | RT | | 18+21.60 | RT | 22 |
| 17+50.95 | LT | | 18+50.69 | LT | 101 |
| 21+46.86 | RT | | 22+36.30 | RT | 91 |
| 21+78.28 | LT | | 22+50.00 | LT | 72 |
| TOTAL | | | | | 285 |
| SAY | | | | | 287.5 |

| MEDIAN REMOVAL (44003100) | | | | | | |
|---------------------------|--|-------|----------|--|------------|------|
| STA | | WIDTH | STA | | AREA SQ FT | |
| 10+25.00 | | 4 | 17+50.00 | | 4 | 2900 |
| 17+50.00 | | 4 | 18+64.00 | | 4 | 456 |
| 21+35.95 | | 4 | 22+50.00 | | 4 | 456 |
| 22+50.00 | | 4.2 | 25+00.00 | | 4.2 | 1050 |
| 25+00.00 | | 4.2 | 27+85.00 | | 10.3 | 2067 |
| TOTAL | | | | | 6929 | |

| CONCRETE MEDIAN, TYPE SB-6.06 (60619200) | | | | | | |
|--|--------|-------|----------|--------|-------|------------|
| STA | | WIDTH | STA | | WIDTH | AREA SQ FT |
| 10+25.00 | CENTER | 4 | 17+50.00 | CENTER | 4 | 2900 |
| 17+50.00 | CENTER | 4 | 18+57.07 | CENTER | 4 | 428 |
| 21+43.15 | CENTER | 4 | 22+50.00 | CENTER | 4 | 427 |
| 22+50.00 | CENTER | 4.2 | 25+00.00 | CENTER | 4.2 | 1050 |
| 25+00.00 | CENTER | 4.2 | 27+85.00 | CENTER | 10.3 | 2067 |
| TOTAL | | | | | | 6872 |

BOWMAN, BARRETT & ASSOCIATES INC
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



| | | | |
|---------------------------------------|---------------------|-----------------|----------------------|
| FILE NAME = D:\B0005-shr-schedule.dgn | USER NAME = default | DESIGNED - | REVISED - 05/22/2009 |
| | | DRAWN - RA | REVISED - |
| | | CHECKED - RS | REVISED - |
| | | DATE - 5/6/2009 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

| | | | | | | | |
|-----------|-------------------------|--------------------|----------------|-------------------|-------------|---|-------------|
| SCALE: NA | SHEET NO. 1 OF 4 SHEETS | STA. NA TO STA. NA | F.A. RTE. 0353 | SECTION 0303.1B-1 | COUNTY COOK | TOTAL SHEETS 91 | SHEET NO. 6 |
| | | | | | | CONTRACT NO. 60C05 | |
| | | | | | | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | |