

| PERIMETER EROSION BARRIER (28000400) | | | | | | | |
|--------------------------------------|--------|----|----|----------|--------|----|------|
| STA | OFFSET | | TO | STA | OFFSET | | FOOT |
| 17+07.43 | 42.5 | RT | | 17+09.33 | 68.1 | RT | 26 |
| 17+09.33 | 68.1 | RT | | 18+33.06 | 62.3 | RT | 124 |
| 18+33.06 | 62.3 | RT | | 19+36.52 | 62.2 | RT | 103 |
| 19+36.52 | 62.2 | RT | | 19+35.14 | 62.3 | LT | 65 |
| 19+35.14 | 62.3 | LT | | 18+18.70 | 62.3 | LT | 117 |
| 18+18.70 | 62.3 | LT | | 17+39.54 | 66 | LT | 80 |
| 17+39.54 | 66 | LT | | 17+34.87 | 41.6 | LT | 25 |
| 20+64.77 | 62.2 | RT | | 22+49.72 | 65 | RT | 186 |
| 22+49.72 | 65 | RT | | 22+54.61 | 40.6 | RT | 26 |
| 20+64.77 | 62.2 | RT | | 20+63.58 | 62.3 | LT | 65 |
| 20+63.58 | 62.3 | LT | | 22+18.85 | 62.3 | LT | 155 |
| 22+18.85 | 62.3 | LT | | 23+27.46 | 70.6 | LT | 109 |
| 23+27.46 | 70.6 | LT | | 23+34.02 | 46.9 | LT | 25 |
| 293+10± | I-394 | RT | | | | | 56 |
| 297+80± | I-394 | LT | | | | | 56 |
| TOTAL | | | | | | | 1216 |

| SEEDING, CLASS 2A (25000210) | | | | | | | | | | SQ YD 25100630 EROSION CONTROL BLANKET AREA SQ YD | POUND 25000400 NITROGEN FERTILIZER NUTRIENT ACRE * 90 RATE | POUND 25000500 PHOSPHORUS FERTILIZER NUTRIENT ACRE * 90 RATE | POUND 25000600 POTASSIUM FERTILIZER NUTRIENT ACRE * 90 RATE |
|------------------------------|--------|----|----|----------|--------|----|---------------|---------------------|-------|--|---|---|--|
| STA | OFFSET | | TO | STA | OFFSET | | AREA SQ FT | ACRE SQ FT/43560 | | | | | |
| 17+10.80 | 50.7 | RT | | 17+50.00 | 50.6 | RT | | | | | | | |
| 17+50.00 | 50.6 | RT | | 18+00.00 | 42 | RT | | | | | | | |
| 18+00.00 | 42 | RT | | 18+50.00 | 39.4 | RT | | | | | | | |
| 18+50.00 | 39.4 | RT | | 19+39.40 | 39.1 | RT | 1190 | 0.03 | 132.2 | 2.5 | 2.5 | 2.5 | |
| 20+61.70 | 42.9 | RT | | 21+43.07 | 42.9 | RT | | | | | | | |
| 21+43.07 | 42.9 | RT | | 22+00.00 | 37.9 | RT | | | | | | | |
| 22+00.00 | 37.9 | RT | | 22+50.00 | 47 | RT | 1152 | 0.03 | 128.0 | 2.4 | 2.4 | 2.4 | |
| 17+39.38 | 48.3 | LT | | 18+00.00 | 38.9 | LT | | | | | | | |
| 18+00.00 | 38.9 | LT | | 18+50.00 | 41.8 | LT | | | | | | | |
| 18+50.00 | 41.8 | LT | | 18+57.17 | 46.8 | LT | | | | | | | |
| 18+57.17 | 46.8 | LT | | 19+39.40 | 46.8 | LT | 1642 | 0.04 | 182.4 | 3.4 | 3.4 | 3.4 | |
| 20+60.70 | 41.6 | LT | | 21+43.07 | 41.6 | LT | | | | | | | |
| 21+43.07 | 41.6 | LT | | 21+50.00 | 37.1 | LT | | | | | | | |
| 21+50.00 | 37.1 | LT | | 22+00.00 | 41.7 | LT | | | | | | | |
| 22+00.00 | 41.7 | LT | | 22+50.00 | 48.4 | LT | | | | | | | |
| 22+50.00 | 48.4 | LT | | 22+97.99 | 52 | LT | 1452 | 0.03 | 161.3 | 3.0 | 3.0 | 3.0 | |
| 293+10± | I-394 | RT | | | | | 362 | 0.01 | 40.3 | 0.7 | 0.7 | 0.7 | |
| 297+80± | I-394 | LT | | | | | 362 | 0.01 | 40.3 | 0.7 | 0.7 | 0.7 | |
| TOTAL | | | | | | | 6161 | 0.25 | 685 | 13 | 13 | 13 | |

| STATION | OFFSET | SIGN PANEL-TYPE 3 (72000300) SQ FT | STRUCTURAL STEEL SIGN SUPPORT-BREAKAWAY (72700100) POUND | CONCRETE FOUNDATIONS (73400100) CU YD | REINFORCEMENT BARS, EPOXY COATED (50800205) POUND | RELOCATE SIGN PANEL-TYPE 3 (72400730) SQ FT |
|-----------------|------------|---|---|--|---|--|
| 16+00.00 | 43.4'LT ± | 104 | 540 [2 POSTS W6X15] | 1.4 | 156 | 0 |
| 24+00.00 | 43.4'RT ± | 104 | 555 [2 POSTS W6X15] | 1.4 | 156 | 0 |
| IB016S394L005.0 | | 156 | 0 | 0 | 0 | 0 |
| IB016S394R005.0 | | 195 | 0 | 0 | 0 | 0 |
| MOT PLANS | | | | | | |
| 296+20.00 | IL 394, LT | | 590.4 | 1.5 | 155 | 156 |
| 294+20.00 | IL 394, RT | | 636.5 | 1.5 | 155 | 195 |
| TOTAL | | 559 | 2322 | 6 | 622 | 351 |

| EARTHWORK SCHEDULE (20200100) | | | | |
|-------------------------------|---------------------------|--|------------------|--|
| STA | 25% SHRINKAGE FACTOR | | EMBANKMENT CY | EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CY |
| | EARTH EXCAVATION CY | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CY | | |
| PRE-STAGE | | | | |
| 16+05 to 16+53 | 12 | 9.00 | 0 | 9.00 |
| 23+53 to 24+50 | 22 | 16.50 | 0 | 16.50 |
| 12+20 TO 16+51 | 91 | 68.25 | 0 | 68.25 |
| 23+60 TO 23+81 | 3 | 2.25 | 0 | 2.25 |
| SLOPE WALL | 120 | 90 | 0 | 90.00 |
| 17+39.00 | - | - | - | - |
| 17+50.00 | - | - | - | - |
| 17+10.75 | - | - | - | - |
| 17+50.00 | - | - | - | - |
| 17+50.00 | - | - | - | - |
| 18+00.00 | 157.39 | 118.04 | 0 | 118.04 |
| 18+50.00 | 145.72 | 109.29 | 0 | 109.29 |
| 18+57.17 | 24.38 | 18.28 | 0 | 18.28 |
| 18+87.17 | 59.32 | 44.49 | 0 | 44.49 |
| 21+13.07 | | | | |
| 21+43.07 | 58.24 | 43.68 | 0 | 43.68 |
| 21+50.00 | 25.45 | 19.09 | 0 | 19.09 |
| 22+00.00 | 180.43 | 135.32 | 0 | 135.32 |
| 22+50.00 | 207.54 | 155.65 | 0 | 155.65 |
| 23+00.00 | 0 | 0.00 | 0 | 0.00 |
| 23+28.46 | 0 | 0.00 | 0 | 0.00 |
| 293+10± I-394 RT | 2.15 | 1.61 | 0 | 1.61 |
| 297+80± I-394 RT | 2.15 | 1.61 | 0 | 1.61 |
| TOTAL | 1111 | 833 | 0 | 833 |

| PROTECTIVE COAT (42001300) | | | | | | |
|----------------------------|--------|---------|----------|--------|---------|--------|
| STA | | SURFACE | STA | | SURFACE | SY |
| 17+50.00 | CENTER | 4.5 | 18+57.07 | CENTER | 4.5 | 53.5 |
| 21+43.15 | CENTER | 4.5 | 22+50.00 | CENTER | 4.5 | 53.4 |
| CURB AND GUTTER | | | | | | |
| 16+05.00 | LT | | 16+53.00 | LT | | 5.3 |
| 23+53.00 | LT | | 24+50.00 | LT | | 27.0 |
| 12+20.00 | RT | | 16+51.00 | RT | | 49.0 |
| 23+60.00 | RT | | 23+81.00 | RT | | 1.8 |
| MEDIAN | | | | | | |
| 09+70.00 | | | 17+55.00 | CENTER | | 499.0 |
| 22+50.00 | | | 29+90.00 | CENTER | | 1436.0 |
| TOTAL | | | | | | 2125 |

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com



| | | | | | | | | | | | | |
|---------------------------------------|---------------------|-----------------|----------------------|---|-------------------------------|-------------------------|--------------------|---------------------|---------------------------|--------|-----------------|--------------|
| FILE NAME = D:\B0C05-shr-schedule.dgn | USER NAME = default | DESIGNED - | REVISED - 05/22/2009 | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SCHEDULE OF QUANTITIES | | | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | | DRAWN - RA | REVISED - | | 0353 | 0303.1B-1 | COOK | 91 | 7 | | | |
| | | CHECKED - RS | REVISED - | | CONTRACT NO. 60C05 | | | | | | | |
| | | DATE - 5/6/2009 | REVISED - | | SCALE: NA | SHEET NO. 2 OF 4 SHEETS | STA. NA TO STA. NA | FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT | | | |

s:\10\05-CADD\US30\CADD Sheets\1166205-shr-schedule.dgn